



**GUTTER OUTLET, SPL
DETAIL**

NOTES:

1. OUTLET TO FOLLOW BD-03 DETAIL ON SHEET 57. CONTRACTOR TO INCREASE LENGTH OF GUTTER OUTLET FROM 18' TO 30' BASED ON PROPOSED LONGITUDINAL SLOPE OF 3.74% PER GENERAL NOTE ON BD-03 DETAIL.
2. GUTTER OUTLET TO BE CONSTRUCTED BETWEEN GUARDRAIL POSTS. ENGINEER TO VERIFY DIMENSIONS AND POST SPACINGS AS SHOWN WITH APPLICABLE HIGHWAY STANDARDS 630001, 631032, AND BD-03 PRIOR TO POURING OF CONCRETE.
3. GUTTER OUTLET TO BE PAID FOR AS GUTTER OUTLET (SPECIAL) AS DESCRIBED IN THE PROJECT SPECIFICATIONS.

FILE NAME = W:\755-610 Blvin Phase II\CADD\Sheets\755-610-55-ghr-det1.dgn

B Bollinger, Lach
& Associates, Inc.
ITASCA, ILLINOIS

USER NAME = dbruckelmeyer	DESIGNED - DBB	REVISED -
PLOT SCALE = 20.0000' / IN.	DRAWN - DBB	REVISED -
PLOT DATE = 3/25/2011	CHECKED - CRF	REVISED -
	DATE - 03-28-11	REVISED -

**BLVIN STREET OVER
NIPPERSINK CREEK**

CONSTRUCTION DETAILS

SCALE: 1"=20' SHEET NO. 55 OF 69 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	08-00355-00-BR	MCHENRY	69	55
CONTRACT NO. 63583				
FED ROAD DIST NO. 1 ILLINOIS FED AID PROJECT				