

SUMMARY OF QUANTITIES

PAY ITEM #	ITEM	UNIT	0004 TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	610
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	350
20800150	TRENCH BACKFILL	CU YD	135
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1000
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	5850
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	110
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	110
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	110
25200110	SODDING, SALT TOLERANT	SQ YD	5850
25200200	SUPPLEMENTAL WATERING	UNIT	100
28000400	PERIMETER EROSION BARRIER	FOOT	4150
28000510	INLET FILTERS	EACH	7
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	525
35800100	PREPARATION OF BASE	SQ YD	10300
35800200	AGGREGATE BASE READY AIR	TON	500
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1030
40600300	AGGREGATE (PRIME COAT)	TON	25
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	10
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	20
40701801	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 6"	SQ YD	10300
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	475
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	4350
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	300
42400800	DETECTABLE WARNING ISLANDS	SQ FT	112
44000100	PAVEMENT REMOVAL	SQ YD	10300
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	145
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	475
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	4500
44000600	SIDEWALK REMOVAL	SQ FT	750
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	731
60201110	CATCH BASINS, TYPE 1, 4'-DIAMETER, TYPE 11V FRAME AND GRATE	EACH	4
60236825	INLETS, TYPE A, TYPE 11V FRAME AND GRATE	EACH	3
60255500	MANHOLES TO BE ADJUSTED	EACH	2
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	3
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	4500
67100100	MOBILIZATION	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12
# 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	380
# 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5165
# 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	20
# 78000850	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	30
78300100	PAVEMENT MARKING REMOVAL	SQ FT	60
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	11
X4023000	TEMPORARY ACCESS (ROAD)	EACH	5
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	350
A Z0076600	TRAINEES	hour	500

* DENOTE SPECIAL PROVISION
DENOTES SPECIAL ITEM
Δ CONSTRUCTION CODE TYPE 0042

FILE NAME = N:\CRESTHILL\100397\Civil\100397.DGN	USER NAME = CMCOLLO	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES CEDARWOOD DRIVE, CRESTHILL	F.A. RTE. 328	SECTION 10-00040-00-PV	COUNTY WILL	TOTAL SHEETS 31	SHEET NO. 3		
PLOT SCALE = 1"	CHECKED -	REVISED -	SCALE:			SHEET NO. 1 OF 1 SHEETS	STA. TO STA.	CONTRACT NO. 63586				
PLOT DATE = 4/8/2011	DATE -	REVISED -	ILLINOIS FED. AID PROJECT									