

SUMMARY OF QUANTITIES

SPECIALTY ITEMS	CODE NUMBER	PAY ITEM	UNIT	QUANTITY	Construction Code Type 0014
*	28000400	PERIMETER EROSION BARRIER	FOOT	380	380
*	31101300	SUBBASE GRANULAR MATERIAL, TYPE B 5"	SQ YD	141	141
*	31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	53	53
*	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	35	35
*	40701871	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 1/2"	SQ YD	105	105
*	42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	33	33
*	42300100	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 5 INCH	SQ YD	53	53
*	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	400	400
*	44000100	PAVEMENT REMOVAL	SQ YD	306	306
*	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	53	53
*	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	210.8	210.8
*	44000600	SIDEWALK REMOVAL	SQ FT	400	400
	50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1
	50102400	CONCRETE REMOVAL	CU YD	0.8	0.8
	50300225	CONCRETE STRUCTURES	CU YD	16.4	16.4
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	84.8	84.8
	50300260	BRIDGE DECK GROOVING	SQ YD	248	248
	50300300	PROTECTIVE COAT	SQ YD	401	401
	50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	1130	1130
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	22700	22700
	50800515	BAR SPLICERS	EACH	54	54
	51500100	NAME PLATES	EACH	1	1
*	60251730	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	2	2
*	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1	1
	67100100	MOBILIZATION	L SUM	1	1
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
*	X0325670	CONCRETE BRIDGE RAIL, SIDEWALK MOUNTED	FOOT	71	71
	X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	99	99
*	X6063401	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.12	FOOT	210.8	210.8
	X6640304	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	FOOT	40	40
	Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	196	196
	Z0073700	TEMPORARY WALL BRACING SYSTEM	L SUM	1	1
	XX006119	TRAFFIC CONTROL AND PROTECTION (DETOUR)	L SUM	1	1

PLAN	DATE
NO.	
BY	
DATE	
NO.	
BY	
DATE	
NO.	
BY	
DATE	
NO.	

PROFILE	DATE
NO.	
BY	
DATE	
NO.	
BY	
DATE	
NO.	
BY	
DATE	
NO.	

FILE NAME: #FILE#

URS
100 S. WACKER DR.
SUITE 500
CHICAGO, IL 60606
TEL (312) 939-1000
FAX (312) 939-4198

USER NAME =	DESIGNED <i>L. LAWS</i>	REVISED -
PLOT SCALE = *SCALE*	DRAWN <i>1/15/11</i>	REVISED -
PLOT DATE = *DATE*	CHECKED <i>J. BUCHOLC</i>	REVISED -
	DATE <i>1/28/11</i>	REVISED -

**VILLAGE OF DEERFIELD
JUNIPER COURT OVER THE WEST FORK,
NORTH BRANCH OF THE CHICAGO RIVER**

SCALE:	SHEET NO. 3 OF 16 SHEETS	STA. TO STA.
--------	--------------------------	--------------

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	09-00084-00-BR	LAKE	16	3
CONTRACT NO. 63587				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				