

EARTHWORK SCHEDULE - II. 2

LOCATION	20200100	EARTH	EMBANKMENT	EARTHWORK	ROCK	ROCK	ROCK	20201200	2000226	21101625	21101645	25000100	25400201		
	EARTH	EXCAVATION												EXCAVATION	BALANCE
	EXCAVATION	ADJUSTED FOR		(+) OR	WEATHERED	SOLID	SOLID	DISPOSAL OF	EMBRANKMENT	FURNISH AND	FURNISH AND	CLASS 1	MOWING		
	CU YD	SHRINKAGE 25%	CU YD	SHORTAGE (-)	ADJUSTED FOR			UNSUITABLE	CU YD	PLACE, 6-INCHES	PLACE, 12-INCHES	ACRE	STAKES		
					SWELL 15%			MATERIAL							
					CU YD			CU YD							
ILLINOIS ROUTE 2	ELMWOOD 695+00		755	566	-2								3		
	695+00 700+00		5,633	4,225	-78								3		
	700+00 705+00		679	509	-4								3		
	705+00 710+00		1,822	1,367	-35								6		
	710+00 715+00		5,333	4,000	-930						2,000	0.01	10		
	715+00 720+00		3,215	2,411	-10,555						3,478	0.18	10		
	720+00 725+00		15,980	11,985	-5,150						8,933	0.26	10		
	725+00 730+00		44,840	33,630	-176						3,606	4,144	0.02	10	
	730+00 735+00		40,832	30,624	-29							12,278	0.33	10	
	735+00 740+00		33,848	25,386	-532							10,639	0.40	10	
	740+00 742+30		956	717	-26,369							10,211	0.42	4	
	743+45 745+00		117	88	-9,069									4	
	745+00 750+00		17,315	12,986	-30,920									10	
	750+00 755+00		65,739	49,304	49,304									15	
	755+00 760+00		22,211	16,658	-46									10	
	760+00 765+00		17,611	13,208	-5,605									4	
	765+00 770+00		15,170	11,378	-6,582									5	
	770+00 775+00		2,813	2,110	-8,307									10	
	775+00 780+00		7,894	5,921	-5,221									10	
	780+00 785+00		2,697	2,023	-12,344									10	
	785+00 790+00		8,554	6,416	-12,874									10	
	790+00 795+00		5,407	4,055	-12,332									10	
	795+00 800+00		3,392	2,544	-10,535									10	
	800+00 805+00		26,041	19,531	-2,131									10	
	805+00 810+00		29,759	22,319	-393									10	
	810+00 815+00		25,469	19,102	-241		367	422	348	400				10	
	815+00 820+00		17,922	13,442	-2,815		913	1,050	754	867				6	
	820+00 825+00		2,700	2,025	-22,117									10	
825+00 830+00		3,104	2,328	-18,017									10		
830+00 835+00		3,373	2,530	-16,597									10		
835+00 840+00		11,931	8,948	-2,116									10		
840+00 845+00		33,385	25,039	-2									10		
845+00 850+00		8,396	6,297	-581									10		
850+00 855+00		3,542	2,657	-614									5		
TEMPORARY CROSSOVER		6,891	5,168	-940											
SUB-TOTAL		495,326	371,495	-224,259		1,280	1,472	1,102	1,267	68,617	74,857	210,856	96,356	8.68	282
OLD RIVER RD. STAGE 1	1346+00 1351+00		702	527										6	
	1351+00 1355+00		1,275	956	-4									3	
	SUB-TOTAL		1,977	1,483	-4										
OLD RIVER RD. STAGE 2 AND 2A	1342+00 1344+00		1,386	1,040	-4,279									0	
	1346+00 1351+00		1,697	1,273	-1,114									6	
	1351+00 1355+00		405	304	-981									3	
	SUB-TOTAL		3,488	2,616	-6,374										9
CASTLE DRIVE	300+11 305+00		473	355	-2,896									8	
	305+00 311+02		1,621	1,216	-4,404									10	
	SUB-TOTAL		2,094	1,571	-7,300										
BAUER PKWY	995+50 999+30		6,909	5,182	-24									6	
	SUB-TOTAL		6,909	5,182	-24										
LATHAM ROAD	STAGE 1														
	1646+62 1650+00		1,336	1,002	-93									6	
	1650+00 1655+00		4,612	3,459	-110									10	
	1655+00 1660+00		3,765	2,824	-657									10	
	1660+00 1665+00		7,395	5,546	-1,264									0	
	1665+00 1670+00		30,691	23,018										8	
	1670+00 1674+00		11,761	8,821	-1,196		489	562	543	624				4	
	STAGE 1 SUBTOTAL														
	STAGE 2														
	1674+00 1680+00		568	426	-12,572		22							10	
	1680+00 1685+00		781	586	-10,678									6	
	1685+00 1690+00		872	654	-7,328									10	
	1690+00 1695+00		2,502	1,877	-1,911									10	
	1695+00 1700+53		3,054	2,291	-1,276									10	
STAGE 2 SUBTOTAL		7,777	5,833	-33,765		22	26						10		
SUB-TOTAL		67,337	50,503	-37,085		511	588	543	624					84	



Revised 6/1/2011, GC

I:\projects\125A\Segment\_1\Inhouse\Civil\Map\total25rcteng\ldp

USER NAME = thompson	DESIGNED RDT/GC	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	ILLINOIS ROUTE 2 SCHEDULE OF QUANTITIES - 2			F.A.P. RTE. 734	SECTION 77-2-2 & 77-2B-1	COUNTY WINNEBAGO	TOTAL SHEETS 530	SHEET NO. 16	
PLOT SCALE = 50.0001 FT / IN.	CHECKED GC	REVISED -		SCALE: N.T.S.	SHEET NO. 16 OF 530 SHEETS	STA. TO STA.	CONTRACT NO. 64813					
PLOT DATE = 6/2/2011	DATE 01-14-11	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								