

SUMMARY OF QUANTITIES CONTINUED

ITEM #	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	80% FED. / 20% STATE				100% STATE BOX CULVERTS TO BE CLEANED	BAUER ROAD 80% Federal 10% State 10% County	0021 OLD RIVER RD 80% Federal 20% State	LATHAM ROAD 80% Federal 10% State 10% County
				0003 ROADWAY	0003 DETOUR ROUTE	0008 MUD CREEK BRIDGE SN 101-0177 AND SN 101-0178	0040 BOX CULVERTS				
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	181	181							
60100945	PIPE DRAINS 12"	FOOT	131	131							
60107600	PIPE UNDERDRAINS 4"	FOOT	58,521	58,521							
60107700	PIPE UNDERDRAINS 6"	FOOT	50	50							
60107800	PIPE UNDERDRAINS 8"	FOOT	50	50							
60107900	PIPE UNDERDRAINS 10"	FOOT	50	50							
60108000	PIPE UNDERDRAINS 12"	FOOT	50	50							
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	3,395	3,395							
20046304	PIPE UNDERDRAINS FOR STRUCTURES, 4"	FOOT	261			261					
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2							
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1							
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1	1							
60236600	INLETS, TYPE A, TYPE 9 FRAME AND GRATE	EACH	2	2							
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	8	8							
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	3	3							
60500060	REMOVING INLETS	EACH	2	2							
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	14.1	14.1							
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	786.5	786.5							
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	357.5	357.5							
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	651	651							
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	44,914	44,914							
60622320	CONCRETE MEDIAN, TYPE SM-4.24	SQ FT	25,172	25,172							
60623200	CONCRETE MEDIAN, TYPE SM-6.24	SQ FT	2,067	2,067							
60624600	CORRUGATED MEDIAN	SQ FT	2,089	2,089							
60900515	CONCRETE THRUST BLOCKS	EACH	4			4					
61000115	TYPE E INLET BOX, STANDARD 610001	EACH	2			2					
61000225	TYPE F INLET BOX, STANDARD 610001	EACH	2			2					
61100605	MISCELLANEOUS CONCRETE	CU YD	5	5							
61101007	STORM SEWERS PROTECTED, CLASS A, 6"	FOOT	50	50							
61101009	STORM SEWERS PROTECTED, CLASS A, 8"	FOOT	50	50							
61101011	STORM SEWERS PROTECTED, CLASS A, 10"	FOOT	50	50							
61101013	STORM SEWERS PROTECTED, CLASS A, 12"	FOOT	50	50							
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	5	5							
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1,987.5	1,987.5							
63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	25.0	25.0							
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	6	6							
63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	4	4							
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4							
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	7	7							
63200310	GUARDRAIL REMOVAL	FOOT	2,651	2,651							

*Specialty Items

I:\projects\1125A\viewment\1\sheeta\civil\mso\25\sum01.dgn

USER NAME = thompard	DESIGNED RDT/GC	REVISED -
PLOT SCALE = 50,000 FT / IN.	DRAWN RDT	REVISED -
PLOT DATE = 2/3/2011	CHECKED GC	REVISED -
	DATE 01-14-11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

ILLINOIS ROUTE 2 SUMMARY OF QUANTITIES - 4			
SCALE: N.T.S.	SHEET NO. 9 OF 530 SHEETS	STA.	TO STA.

F.A.P. RTE. 734	SECTION 77-2-2 & 77-2B-1	COUNTY WINNEBAGO	TOTAL SHEETS 530	SHEET NO. 9
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 64813				