

64200105 - SHOULDER RUMBLE STRIP

LOCATION	LENGTH (FEET)
IL ROUTE 2 NORTHBOUND	
708+20.00 TO 711+50.00 RT	330
709+50.00 TO 711+50.00 LT	200
711+50.00 TO 714+88.85 RT	339
711+50.00 TO 715+50.00 LT	400
724+09.77 TO 726+50.00 LT	240
723+50.00 TO 726+50.00 RT	300
726+50.00 TO 741+50.00 LT	1,500
726+50.00 TO 741+50.00 RT	1,500
741+50.00 TO 742+16.71 RT	67
741+50.00 TO 742+16.71 LT	67
743+89.71 TO 756+50.00 RT	1,260
743+89.71 TO 756+50.00 LT	1,260
756+50.00 TO 756+90.68 RT	41
756+50.00 TO 757+49.50 LT	100
765+99.48 TO 771+00.00 RT	501
766+07.43 TO 771+00.00 LT	493
771+00.00 TO 785+50.00 RT	1,450
771+00.00 TO 785+50.00 LT	1,450
785+50.00 TO 800+50.00 LT	1,500
785+50.00 TO 800+50.00 RT	1,500
800+50.00 TO 809+45.58 RT	896
800+50.00 TO 810+03.80 LT	954
820+27.63 TO 829+50.00 RT	922
819+13.75 TO 829+50.00 LT	1,036
829+50.00 TO 838+80.30 RT	930
829+50.00 TO 838+80.30 LT	930
IL ROUTE 2 SOUTHBOUND	
707+80.00 TO 711+50.00 LT	370
709+50.00 TO 711+50.00 RT	200
711+50.00 TO 720+27.31 LT	877
711+50.00 TO 720+24.08 RT	874
729+36.00 TO 741+50.00 LT	1,214
728+74.75 TO 741+50.00 RT	1,275
741+50.00 TO 742+16.71 LT	67
741+50.00 TO 742+16.71 RT	67
743+89.71 TO 756+50.00 LT	1,260
743+89.71 TO 756+50.00 RT	1,260
756+50.00 TO 762+22.77 LT	573
756+50.00 TO 762+14.91 RT	565
770+72.83 TO 771+00.00 RT	27
771+00.00 TO 785+50.00 RT	1,450
771+28.72 TO 785+50.00 LT	1,421
785+50.00 TO 800+50.00 RT	1,500
785+50.00 TO 800+50.00 LT	1,500
800+50.00 TO 813+54.94 LT	1,305
800+50.00 TO 814+68.80 RT	1,419
823+78.75 TO 829+50.00 RT	571
824+36.61 TO 829+50.00 LT	513
829+50.00 TO 838+80.30 RT	930
829+50.00 TO 838+80.30 LT	930

SHOULDER RUMBLE STRIP, TOTAL = 40,335 FOOT

PIPE UNDERDRAIN QUANTITIES

LOCATION	60100060 - CONCRETE HEADWALL FOR PIPE DRAINS (EACH)	60107600 - PIPE UNDERDRAINS, 4" (FOOT)	60108100 - PIPE UNDERDRAINS 4" (SPECIAL) (FOOT)
MAINLINE STA 696+15 TO 711+50	1	1630	19
MAINLINE STA 711+50 TO 726+50	16	4808	304
MAINLINE STA 726+50 TO 741+50	20	6000	380
MAINLINE STA 741+50 TO 756+50	20	5308	380
MAINLINE STA 756+50 TO 771+00	12	4594	228
MAINLINE STA 771+00 TO 785+50	16	5800	320
MAINLINE STA 785+50 TO 800+50	20	6000	320
MAINLINE STA 800+50 TO 815+00	18	5738	342
MAINLINE STA 815+00 TO 829+50	12	4395	228
MAINLINE STA 829+50 TO 844+25	16	4800	304
LATHAM ROAD STA 1646+62 TO STA 1654+00	4	1476	76
LATHAM ROAD STA 1654+00 TO STA 1668+50	8	2723	152
LATHAM ROAD STA 1668+50 TO STA 1680+00	6	1632	114
LATHAM ROAD STA 1680+00 TO STA 1694+00	10	2311	190
LATHAM ROAD STA 1694+00 TO STA 1700+53	2	1306	38
TOTAL	181	58,521	3,395

Z0005400 - BREAKER-RUN CRUSHED STONE

LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	VOLUME (CU YD)	WEIGHT (TON)
IL ROUTE 2				
772+50	173	19	122	250
783+46	209	18	209	428
837+28	141	11	57	118
FRONTAGE ROAD C				
166+26	63.5	32.5	76	157
DRIVEWAY E				
57+38	50.7	11	21	42

BREAKER-RUN CRUSHED STONE, TOTAL = 995 TON

BUILDING REMOVAL

LOCATION	Z0007603 - BUILDING REMOVAL NO. 3	Z0007605 - BUILDING REMOVAL NO. 5	Z0007606 - BUILDING REMOVAL NO. 6	Z0007607 - BUILDING REMOVAL NO. 7	Z0007608 - BUILDING REMOVAL NO. 8	Z0007609 - BUILDING REMOVAL NO. 9	Z0007610 - BUILDING REMOVAL NO. 10
L SUM							
STA. 764+54 76' RT IL RTE 2		1					
STA. 764+53 3' RT IL RTE 2			1				
STA. 764+50 117' LT IL RTE 2				1			
STA. 764+72 155' LT IL RTE 2					1		
STA. 766+30 22' RT IL RTE 2							1
STA. 765+95 18' LT IL RTE 2						1	
STA. 766+49 75' LT IL RTE 2	1						
TOTAL =	1	1	1	1	1	1	1

Z0023900 - FILLING EXISTING WELLS

LOCATION	(EACH)
BUILDING REM #5	1
BUILDING REM #7	1
BUILDING REM #10	1

FILLING EXISTING WELLS, TOTAL = 3 EACH

Z0106800 - CHANGEABLE MESSAGE SIGN

LOCATION	CAL MO
STAGE 1 DETOUR (2 signs at 3 location) x 0.5 month	3
STAGE 2 DETOUR (2 signs at 3 location) x 0.5 month	3
SB IL ROUTE 2 STAGE 2 (2 signs x 8 month)	16

CHANGEABLE MESSAGE SIGN, TOTAL = 22 CAL MO

Z0025500 - FURNISHING AND INSTALLING PROPERTY MARKERS

LOCATION	EACH
ILLINOIS ROUTE 2	
711+50.00 TO 726+50.00 RT.	1
726+50.00 TO 741+50.00 LT.	2
726+50.00 TO 741+50.00 RT.	2
741+50.00 TO 756+50.00 RT.	1
785+50.00 TO 800+50.00 LT.	1
844+25.00 TO 856+50.00 RT.	2
LATHAM ROAD	
1654+00.00 TO 1668+50.00 RT.	1

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS, TOTAL = 10 EACH

Z0074100 - TERMINATION OF DEAD END ROADS

63500105 - DELINEATORS

LOCATION	(EACH)	DELINEATORS EACH
114+06 (FR A)	1	2
1027+10 (FR B2)	1	4
150+00 (FR C)	1	4
194+24 (FR C)	1	4
1102+12 (FR D)	1	9
266+63 (FR E)	1	6

TERMINATION OF DEAD END ROADS, TOTAL = 6 EACH

DELINEATORS, TOTAL = 29 EACH

Z0062456 - TEMPORARY PAVEMENT
X4400110 - TEMPORARY PAVEMENT REMOVAL

LOCATION	AREA (SQ. YD.)
STAGE 1 CONSTRUCTION	
IL ROUTE 2	510
TEMPORARY BYPASS ROADWAY	4,018
OLD RIVER ROAD	1,610
STAGE 2 CONSTRUCTION	
IL ROUTE 2	343
OLD RIVER ROAD	255
LATHAM ROAD	17

TEMPORARY PAVEMENT, TOTAL = 6,753 SQ. YD.
TEMPORARY PAVEMENT REMOVAL, 6,753 SQ. YD.

Z0015580 - TREE AND DEBRIS REMOVAL (SPECIAL)

LOCATION	UNIT
IL RTE 2 STA. 796+00, LT	1

TREE AND DEBRIS REMOVAL (SPECIAL), TOTAL = 1 UNIT