



BEGIN IMPROVEMENT  
STA. 1646+62.42

MATCHLINE 1654+00.00  
SEE PAVEMENT MARKING 16

**PAVEMENT MARKING LEGEND**

- ① 4" YELLOW SOLID
  - ② 6" WHITE SKIP DASH
  - ③ 4" WHITE SOLID
  - ④ 4" DOUBLE YELLOW
  - ⑤ 24" WHITE STOP BAR
  - ⑥ 4" YELLOW SKIP DASH
  - ⑦ 8" WHITE SOLID
  - ⑧ 8" WHITE SKIP DASH
  - \* ⑨ 12" WHITE DIAGONAL (20' c-c)  
\* SPA. @ 6' c-c
  - ⑩ 12" YELLOW DIAGONAL (30' c-c)
  - ⑪ ARROWS
- 10' 30' 10'  
 2' 8' 2'  
 20'  
 30'  
 8'  
 8'
- DIRECTION OF TRAVEL  
 ◀ TWO-WAY AMBER MARKER  
 ▶ ONE-WAY AMBER MARKER  
 ▷ ONE-WAY CRYSTAL MARKER  
 RRPM RAISED REFLECTIVE PAVEMENT MARKER

**NOTES:**

1. ALL RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE SPACED AT 80' CENTERS UNLESS OTHERWISE NOTED. (40' CENTERS AT MEDIANS)
2. FOR ALL PAINTED ISLANDS, SEE DISTRICT STD. 93.4
3. FOR ALL PAINTED MEDIANS, SEE DISTRICT STD. 41.1
4. FOR STANDARD SPACING & LOCATION OF RAISED REFLECTIVE PAVEMENT MARKERS, SEE IDOT HIGHWAY STD. 781001
5. CENTERLINE PAVEMENT MARKING ON FRONTAGE ROADS IS SHOWN FOR INFORMATION ONLY. PAVEMENT MARKING FOR THE CENTERLINE SHALL BE DETERMINED IN THE FIELD.
6. ALL PAVEMENT MARKINGS MATERIAL SHALL BE AS SHOWN ON DISTRICT STD. 41.1

I:\pavement\11254\pavement\_16\latham\1654\1654\_rte.pmk-16.rdg

USER NAME = zulkowid	DESIGNED STS/GC	REVISED -
	DRAWN RDT	REVISED -
PLOT SCALE = 50.0000 FT / IN.	CHECKED GC	REVISED -
PLOT DATE = 2/2/2011	DATE 01-14-11	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

ILLINOIS ROUTE 2 PAVEMENT MARKING 15		F.A.P. RTE. 734	SECTION 77-2-2 & 77-2B-1	COUNTY WINNEBAGO	TOTAL SHEETS 530	SHEET NO. 225
LATHAM ROAD STA 1646+62 TO STA 1654+00		SCALE: 1"=50'		SHEET NO. 225 OF 530 SHEETS		STA. TO STA.
		FED. ROAD DIST. NO.		[ILLINOIS] FED. AID PROJECT		

CONTRACT NO. 64813