DRAINAGE SCHEDULE

PAY ITEM NUMBER				X6024246	X6024250	X6024254	X6024256	Z0019500	60236200	60236800	60240215	60240310	60218400	60219300	60221700	60223700	60224446	60224449	54213657	54213660	54213663	54213669	54213675	54213681	Z0065753			
				INLETS AND MANHOLES															FLARED END SECTIONS										
SHEET	DESC.	STATION	OFFSET	INLETS SPL N3 EACH	INLETS SPL N5 EACH	INLETS SPL N7 EACH	INLETS SPL N8 EACH	DRYWELL EACH	INLETS TA T8G EACH	INLETS TA T11F&G EACH	INLETS TB T1F CL EACH	INLETS TB T11F&G EACH	MAN TA 4 DIA T1F CL EACH	MAN TA 4 DIA T11F&G EACH	MAN TA 5 DIA T8G EACH	MAN TA 6 DIA T1F OL EACH	MAN TA 7 DIA T1F CL EACH	MAN TA 7 DIA T24F&G EACH	PRC FLAR END SEC 12 EACH	PRC FLAR END SEC 15 EACH	PRC FLAR END SEC 18 EACH	PRC FLAR END SEC 24 EACH	PRC FLAR END SEC 30 EACH	PRC FLAR END SEC 36 EACH	SLOTTED DRAIN 15" WITH 6" SLOT FEET	OTHER	RIM ELEV	INVERT ELEV	DESC.
D6	1200	52+37.13	48.36' RT																	1								728.52	1200
D6	1201	50+87.38	30.07' RT		1																							732.13	728.79	1201
D6	1202	50+87.38	20.54' LT		1																							732.48	729.01 E & N, 729.26 W	1202
D6	1203	51+48.78	37.31' LT		1																							732.75	729.64	1203
D6	1204	51+60.61	29.42' LT		1																							732.75	729.75	1204
D6	1205	50+90.00	52.76' LT																1										730.64	1205
D6	1300	55+00.00	32.71' RT																	1									728.19	1300
D6	1301	55+00.00	15.00' RT		1																							731.65	728.27	1301
D6	1302	55+00.00	15.00' LT		1																							731.65	728.40 S, 728.65 N	1302
D6	1303	55+21.29	41.59' LT																1										729.7	1303
D6	1400	57+00.00	34.66' RT																1										728.88	1400
D6	1401	57+00.00	15.00' RT		1																							732.11	728.97	1401
D6	1402	57+00.00	15.00' LT		1																							732.11	729.11	1402
D6	1403	56+98.97	36.52' LT																1										729.5	1403
D6	1500	59+00.00	36.89' RT																1										729.64	1500
D6	1501	59+00.00	15.00' RT		1																							732.79	729.74 SE & NW, 729.88 NE	1501
D6	1502	59+00.00	15.00' LT		1																							732.79	729.88	1502
D6	1503	61+00.00	15.00' RT		1																							733.57	730.52	1503
D6	1504	61+00.00	15.00' LT		1																							733.57	730.66	1504
D6	1505	63+25.00	15.00' RT		1																							735.76	732.72	1505
D6	1506	63+25.00	15.00' LT		1																							735.76	732.85	1506
D6	1507	59+00.00	33.45' LT																1										730.03	1507
D3	1600	1008+35.79	5.13' RT																								12" PIPE INTO WALL		729.92	1600
D3	1601	1008+35.06	1.22' LT									1																734.58	730.30 N & SE	1601
D3	1602	1008+37.15	44.22' LT	1																								733.94	730.94 S	1602
D6	1700	54+09.86	40.71'RT																	1									727.90	1700
D6	1701	54+09.86	35.16' LT								1																	733.00	730.10 E, 728.85 S	1701
D6	1702	54+39.92	36.55' LT																						30				730.25 W	1702
D7	1800	869+50.00	98.12' LT																1										729.44	1800
D7	1801	869+92.19	103.77' LT		1																							732.86	729.86	1801
D7	1900	866+04.01	118.38' LT																								EXISTING MH	729.57	725.46 NE	1900
D7	1901	866+32.47	86.32' LT						1																			728.00	725.67	1901
D7	2000	872+00.00	109.87' LT																1										729.44	2000
D7	2001	872+00.00	9.24' RT		1																							733.19	730.19	2001
D2	2100	995+80.50	98.93' RT					1																				727.47		2100
D3	2200	1009+13.33	92.73' RT										1															730.00	725.27 SE & W (MATCH EXISTING)	2200
D3	2201	1008+44.99	102.36' RT																			1							724.55	2201
D3	2300	1009+00.00	87.75' LT																			1					W/ RDWY PER 542301		730.77	2300
D3	2301	1009+32.36	65.39' LT																								PIPE INTO CULVERT		730.22	2301
D3	2500	1009+79.72	120.98' LT																		1								729.00	2500
D3	2501	1009+87.75	96.51' LT																								PIPE INTO WALL		728.50	2501
TOTAL				5	58	1	1	2	3	1	1	8	4	3	1	1	1	1	13	5	3	3	1	0	30	TOTAL			

FILE NAME = D264987-sht-schedule-01.dgn	USER NAME = 320289971	DESIGNED - LOM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	DRAINAGE SCHEDULE	F.A.P RTE. 303	SECTION 129K-1	COUNTY WINNEBAGO	TOTAL SHEETS 401	SHEET NO. 36
		DRAWN - MD	REVISED -							
	PLOT SCALE =	CHECKED - PDK	REVISED -						CONTRACT NO. 64987	
	PLOT DATE = 3/16/2011	DATE - 03-16-2011	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 2	ILLINOIS	FED. AID PROJECT		