

SCHEDULE OF QUANTITIES

LOCATION		PRE-STAGE 1		PRE-STAGE 2		PRE-STAGE 3		WINTER STAGE	
STATION TO STATION	70300280	70301000	70300280	70301000	70300280	70301000	70300280	70301000	
	TEMP PVT MK	WORK ZONE	TEMP PVT MK	WORK ZONE	TEMP PVT MK	WORK ZONE	TEMP PVT MK	WORK ZONE	
	LINE 24	PAVT MK	LINE 24	PAVT MK	LINE 24	PAVT MK	LINE 24	PAVT MK	
	FOOT	SQFT	FOOT	SQFT	FOOT	SQFT	FOOT	SQFT	
RALSTON ROAD/IL 173									
998+00	1013+50	45		36	90	48	72	84	168
1013+50	1028+00	21			72	40		12	24
SUB-TOTAL		66	-	36	162	88	72	96	192

LOCATION		STAGE 1 A		STAGE 1 B		STAGE 1 C		STAGE 2 A		STAGE 2 B		STAGE 2 C		STAGE 3		STAGE 4 A		STAGE 4 B	
STATION TO STATION	70300280	70301000	70300280	70301000	70300280	70301000	70300280	70301000	70300280	70301000	70300280	70301000	70300280	70301000	70300280	70301000	70300280	70301000	
	TEMP PVT MK	WORK ZONE	TEMP PVT MK	WORK ZONE	TEMP PVT MK	WORK ZONE	TEMP PVT MK	WORK ZONE	TEMP PVT MK	WORK ZONE	TEMP PVT MK	WORK ZONE	TEMP PVT MK	WORK ZONE	TEMP PVT MK	WORK ZONE	TEMP PVT MK	WORK ZONE	
	LINE 24	PAVT MK	LINE 24	PAVT MK	LINE 24	PAVT MK	LINE 24	PAVT MK	LINE 24	PAVT MK	LINE 24	PAVT MK	LINE 24	PAVT MK	LINE 24	PAVT MK	LINE 24	PAVT MK	
	FOOT	SQFT	FOOT	SQFT	FOOT	SQFT	FOOT	SQFT	FOOT	SQFT	FOOT	SQFT	FOOT	SQFT	FOOT	SQFT	FOOT	SQFT	
RALSTON ROAD/IL 173																			
980+50	995+50	18													117		73		
995+50	1010+50	139	168	60					118		128	236	58	24	107	23	280	48	
1010+50	1025+50	62							139		12		58	72	107		110	192	24
1025+50	1040+50	48							86				64	48	129			260	
ROUTE 251																			
855+00	868+00	57							84		57	336							
868+00	875+00	70		68	68				136	100			44	120	95		90	134	
875+00	885+00																		
ORLANDO ST																			
74+00	78+00												24	24					
78+00	80+00	12							12	24			14	24	12		32	24	42
N. 2ND FRONTAGE ROAD																			
310+00	313+00	12					12		12	24			32		12		32	24	44
313+00	320+00																		
ALPINE ROAD																			
259+00	266+00																58		
266+00	274+00	49						48	48	48			53	96	48	106	130	96	
274+00	280+00	27											59			118			
SUB-TOTAL		494	168	128	68	12	48	499	232	297	572	406	408	627	224	548	1,010	158	168

70300280 TEMP PVT MK LINE 24 TOTAL =	3,455	ADD 10% =	3,801	FOOT
70301000 WORK ZONE PAVT MK REM SUB-TOTAL =	3,324	SQ FT		

70301000 WORK ZONE PAVT MK REM SUB-TOTAL =	3,375	SQ FT
70301000 WORK ZONE PAVT MK REM SUB-TOTAL =	30,644	SQ FT
70301000 WORK ZONE PAVT MK REM SUB-TOTAL =	8,596	SQ FT
70301000 WORK ZONE PAVT MK REM SUB-TOTAL =	3,324	SQ FT
70301000 WORK ZONE PAVT MK REM TOTAL =	45,940	SQ FT