

SCHEDULE OF QUANTITIES

40600200	<u>BITUMINOUS MATERIALS (PRIME COAT)</u>								
	<u>TON</u>	<u>LOCATION</u>			<u>OFFSET</u>				<u>REMARKS</u>
	1.6	350+25.0	TO	359+75.0					ALL 4 LANES & MEDIAN
	1.6	359+75.0	TO	376+75.0					2 LANES SB
	3.5	376+75.0	TO	394+25.0					ALL 4 LANES & MEDIAN
	0.8	394+25.0	TO	403+25.0					2 LANES SB
	0.3	407+50.0	TO	411+00.0					2 LANES SB
	7.8								
40600525	<u>LEVELING BINDER (HAND METHOD), N50</u>								
	<u>TON</u>	<u>LOCATION</u>			<u>OFFSET</u>				<u>REMARKS</u>
	20.0	TO BE USED AS NEEDED							
40603335	<u>HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50</u>								
	<u>TON</u>	<u>LOCATION</u>			<u>OFFSET</u>				<u>REMARKS</u>
	551.0	350+25.0	TO	359+75.0					ALL 4 LANES & MEDIAN
	444.3	359+75.0	TO	376+75.0					2 LANES SB
	1079.6	376+75.0	TO	394+25.0					ALL 4 LANES & MEDIAN
	235.2	394+25.0	TO	403+25.0					2 LANES SB
	91.4	407+50.0	TO	411+00.0					2 LANES SB
	2401.5								
44000155	<u>HOT-MIX ASPHALT SURFACE REMOVAL 1 1/2"</u>								
	<u>SQ YD</u>	<u>LOCATION</u>			<u>OFFSET</u>				<u>REMARKS</u>
	5623	350+25.0	TO	359+75.0					ALL 4 LANES & MEDIAN
	4533	359+75.0	TO	376+75.0					2 LANES SB
	11017	376+75.0	TO	394+25.0					ALL 4 LANES & MEDIAN
	2400	394+25.0	TO	403+25.0					2 LANES SB
	933	407+50.0	TO	411+00.0					2 LANES SB
	24505								

FILE NAME =	USER NAME = lillyk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL ROUTE 2 SCHEDULE OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
0:\Projects\Winnebago\64H13.Pond.to.Ced	SMART\Meifrich\207811-shk.dgn	DRAWN -	REVISED -			742	(32, 33)RS-3	WINNEBAGO	17	6	
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 64H13					
	PLOT DATE = Thu Mar 10 09:47:02 2011	DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.