

INDEX OF SHEETS

1. Cover Sheet
2. General Notes
3. Summary of Quantities
4. Schedule of Quantities
5. Location Map - Boone County
6. Location Map - Carroll County
7. Location Map - Henry/Rock Island County
8. Sealing detail

GENERAL NOTES

The concrete sealer shall be applied to the entire top surface of the deck, including the inside faces and tops of parapets.

Water based concrete sealers will not be allowed.

Work on this project may potentially conflict with work on other contracts in the area. The contractor should be prepared to plan for potential delays and cooperate with contractors on the other projects.

Existing pavement markings shall be temporarily covered prior to application of the deck surface treatment, to prevent the material from being applied to the markings. The temporary covering shall be removed after application of the deck surface treatment and prior to opening to traffic. Cost included with Concrete Sealer.

HIGHWAY STANDARDS

- 701201-04
- 701400-05
- 701406-06
- 701411-07
- 701421-03
- 701501-06
- 701901-01

FILE NAME =	USER NAME = jinkdj	DESIGNED -	REVISD -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
D:\BR\CADD plans\Various Counties\2011 deck sealing\3rd contract\PLANeng.dgn	DRAWN -	REVISD -	var			D2 DECK SEALING 2011-3	var	8	2	
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISD -	CONTRACT NO. 64H14							
PLOT DATE = Tue Mar 15 13:51:39 2011	DATE -	REVISD -	ILLINOIS FED. AID PROJECT							
					SCALE: _____	SHEET NO. ___ OF ___ SHEETS		STA. _____ TO STA. _____		