

SIDEROAD SCHEDULE								
STATION	RT/LT	DESCRIPTION	AREA	HMA SURF REM	BIT MATL PRIME COAT	AGG PRIME COAT	TEMP RAMP	INC HMA SURF
			SQ YD	1 1/2" SQ YD	GAL	TON	SQ YD	TON
SOUTHBOUND BLOOMINGTON ST								
LASALLE COUNTY								
162+32	LT	Grove St (East)	98	98	8	0.2	14	9
163+70	RT	Boys St. (West)	109	109	9	0.3	21	10
165+41	LT	Bronson St. (East)					19	
167+38	RT	Sumner St.(West)	90	90	8	0.2	12	8
167+38	LT	Sumner St. (East)	116	116	10	0.3	13	10
171+11	RT	Stanton St. (West)	100	100	8	0.2	13	9
171+11	LT	Stanton St. (East)	105	105	9	0.3	13	9
174+86	RT	Grant St. (West)	98	98	8	0.2	13	9
174+86	LT	Grant St. (East)	97	97	8	0.2	14	9
178+60	LT	LaRue St. (East)	85	85	7	0.2	14	8
178+60	RT	LaRue St. (West)	87	87	7	0.2	14	8
182+43	LT	Morrell St. (East)	121	121	10	0.3	24	11
182+43	RT	Morrell St. (West)	157	157	13	0.4	24	14
185+95	RT	Lincoln Ave. (West)	105	105	9	0.3	22	9
185+95	RT	Lincoln Ave. (West)	125	125	10	0.3	21	11
188+68	RT	Broadway St. (West)	99	99	8	0.2	14	9
188+68	LT	Broadway St. (East)	100	100	8	0.2	13	9
197+43	RT	Elm St. (West)	117	117	10	0.3	14	10
197+43	LT	Elm St. (East)	115	115	10	0.3	21	10
201+28	RT	Hickory St. (West)	109	109	9	0.3	21	10
201+28	LT	Hickory St. (East)	160	160	13	0.4	26	14
205+15	RT	Main St (West)	160	160	13	0.4	22	14
205+15	LT	Main St (East)	160	160	13	0.4	22	14
210+72	LT	Bridge St (East)	169	169	14	0.4	22	15
210+72	RT	Bridge St (West)	169	169	14	0.4	22	15
216+69	RT	Wilson St. (West)	91	91	8	0.2	14	8
216+69	LT	Wilson St. (East)	97	97	8	0.2	14	9
220+23	RT	LaSalle St (West)	98	98	8	0.2	14	9
221+85	LT	Livingston St. (East)	95	95	8	0.2	12	8
223+41	RT	Washington St. (west)	107	107	9	0.3	13	9
225+48	LT	Lundy St. (East)	100	100	8	0.2	21	9
226+88	RT	Court St. (West)	105	105	9	0.3	13	9
229+18	LT	Spring St. (East)	105	105	9	0.3	17	9
233+45	RT	6th St. (West)	124	124	10	0.3	18	11
237+07	RT	7th St. (West)	117	117	10	0.3	14	10
240+18	LT	Brumbach St. (East)	90	90	8	0.2	12	8
244+60	LT	Lee St. (East)	92	92	8	0.2	14	8
246+59	RT	9th St. (West)	90	90	8	0.2	14	8
250+46	RT	10th St. (West)	130	130	11	0.3	17	11
250+46	LT	10th St. (East)	98	98	8	0.2	16	9
254+32	RT	11th St. (West)	105	105	9	0.3	13	9
258+22	RT	12th St. (West)	101	101	9	0.3	19	9
LaSalle County Subtotals			4596	4596	384	11.0	703	407
LIVINGSTON COUNTY								
258+22	LT	12th St. (East)	104	104	9	0.3	14	9
	LT	13th St (East)	103	103	9	0.3	24	9
263+15	LT	14th St (East)	84	84	7	0.2	25	8
288+75	RT	Livingston Rd. (West)	115	115	10	0.3	13	10
288+75	LT	Livinsgton Rd (East)	210	210	17	0.5	13	18
292+30	RT	Franklin Rd (West)	150	150	12	0.3	12	13
292+30	LT	Franklin Rd (East)	147	147	12	0.3	13	13
295+94	RT	Adams St. (West)	89	89	8	0.2	13	8
Livingston County Subtotals			1002	1002	84	3.0	127	88
SOUTHBOUND TOTALS			5598	5598	468	14	830	495

SIDEROAD SCHEDULE								
STATION	RT/LT	DESCRIPTION	AREA	HMA SURF REM	BIT MATL PRIME COAT	AGG PRIME COAT	TEMP RAMP	INC HMA SURF
			SQ YD	1 1/2" SQ YD	GAL	TON	SQ YD	TON
NORTHBOUND PARK ST								
LASALLE COUNTY								
497+15	RT	Grove St (West)	84	84	7	0.2	11	8
497+15	LT	Grove St (East)	119	119	10	0.3	12	10
500+19	RT	Bronson St (West)					14	
500+31	LT	Bronson St (East)					14	
502+14	LT	East Sumner St (East)	105	105	9	0.3	11	9
505+90	RT	Stanton St (West)	109	109	9	0.3	12	10
504+50	LT	Stanton St (East)	108	108	9	0.3	12	10
509+67	RT	Grant St (West)	87	87	7	0.2	11	8
508+88	LT	Grant St(East)	105	105	9	0.3	11	9
513+31	RT	LaRue St (West)					17	
513+26	LT	LaRue St (East)					17	
517+21	RT	Morrell St(West)	178	178	15	0.4	23	15
517+28	LT	Morrell St (East)	90	90	8	0.2	22	8
521+00	RT	Lincoln St (West)	157	157	13	0.4	21	14
522+84	RT	Broadway (West)	58	58	5	0.2	12	5
522+84	LT	Broadway (East)	105	105	9	0.3	11	9
528+50	LT	Kent St (East)					22	
528+50	RT	Kent St (West)					22	
532+21	RT	Elm St (West)	100	100	8	0.2	21	9
536+05	RT	Hickory St (West)	97	97	8	0.2	26	9
536+05	LT	Hickory St (East)	145	145	12	0.3	26	13
535+47	LT	NE Hickory/Park Ent	140	140	12	0.3	14	12
539+99	RT	Main St(West)	92	92	8	0.2	29	8
539+99	LT	Main St (East)	126	126	11	0.3	26	11
545+41	RT	Bridge St (West)	242	242	20	0.5	26	21
545+41	LT	Bridge St (East)	165	165	14	0.4	25	14
551+38	RT	Wilson St (West)	144	144	12	0.3	13	13
551+40	LT	Wilson St (East)	158	158	13	0.4	11	14
556+69	RT	Livingston St(West)	96	96	8	0.2	12	9
556+69	LT	Livingston St (East)	85	85	7	0.2	12	8
560+34	RT	Lundy St (West)	150	150	12	0.3	24	13
560+34	LT	Lundy St (East)	166	166	14	0.4	23	14
564+01	RT	Spring St (West)	122	122	10	0.3	17	11
564+01	LT	Spring St(East)	123	123	10	0.3	12	11
575+02	RT	Brumbach St (West)	182	182	15	0.4	19	16
575+02	LT	Brumbach St (East)	100	100	8	0.2	14	9
579+52	RT	Lee St (West)	122	122	10	0.3	12	11
578+60	LT	Cottage St (East)	97	97	8	0.2	11	9
589+06	LT	Sangamon (East)	139	139	12	0.3	12	12
593+15	RT	12th St(West)	96	96	8	0.2	12	9
LaSalle County Subtotal			4192	4192	350	10.0	668	371
LIVINGSTON COUNTY								
593+15	LT	12th St (East)	192	192	16	0.4	13	17
598+07	RT	13th St (West)	87	87	7	0.2	14	8
598+07	LT	13th St (East)	162	162	13	0.4	11	14
603+05	RT	14th St (West)	96	96	8	0.2	11	9
603+05	LT	14th St (East)	115	115	10	0.3	13	10
Livingston County Subtotals			652	652	54	2.0	62	58
NORTHBOUND TOTALS			4844	4844	404	12	731	429