

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				STATE FUNDS	100% STATE
				STRUCTURE	
				0014	RURAL
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	129	129	
40603335	HOT-MIX ASPHALT SURFACE CSE. MIX D, N50	TON	211	211	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL 1 1/2"	SO YD	1607	1607	
44000500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	FOOT	56	56	
50102400	CONCRETE REMOVAL	CU YD	27.1	27.1	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	27	27	
50300300	<i>PROTECTIVE COAT</i>	<i>SO YD</i>	<i>181</i>	<i>181</i>	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	4490	4490	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4010	4010	
50800515	BAR SPLICERS	EACH	48	48	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	188	188	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	14	14	
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	14	14	
52100520	ANCHOR BOLTS 1"	EACH	56	56	
58100200	WATERPROOFING MEMBRANE SYSTEM	SO YD	960	960	
60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	FOOT	56	56	
67100100	MOBILIZATION	L SUM	1	1	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	633	633	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1114	1114	
78005110	EPOXY PAVEMENT MARKING, LINE 4"	FOOT	2132	2132	
78005130	EPOXY PAVEMENT MARKING, LINE 6"	FOOT	800	800	
78300100	PAVEMENT MARKING REMOVAL	SO FT	2304	2304	
X0325598	DRAINAGE SCUPPER DS-12M10	EACH	2	2	
70100325	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423	EACH	1	1	
Z0021904	SILICONE JOINT SEALER, 1"	FOOT	130	130	
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	28	28	
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SO YD	20	20	
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SO YD	960	960	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SO YD	20	20	
Z0012750	CONCRETE MEDIAN REPAIR	SO FT	68	68	
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5")	SO FT	50	50	
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5")	SO FT	68	68	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2	2	

*SPECIALTY ITEMS

FILE NAME =	USER NAME = woodshankr1	DESIGNED - RLW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
o:\pwork\pwork\woodshankr1\d0257390	366937-details.dgn	DRAWN - RLW	REVISED -				68	(68-11)	LASALLE	20	3
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -	REVISED -		SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.		CONTRACT NO. 66937	
PLOT DATE = Apr 08, 2011 - 01:05:10 PM	DATE -	REVISED -	REVISED -		ILLINOIS FED. AID PROJECT						

Rev.