

80% FED./20% STATE  
URBAN

SUMMARY OF QUANTITIES			
CODE NO.	ITEM	ROADWAY 0005	
		UNIT	TOTAL QUANTITY
25200200	SUPPLEMENTAL WATERING	UNIT	1
25200110	SODDING, SALT TOLERANT	SQ YD	21
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4748
40600300	AGGREGATE (PRIME COAT)	TON	74
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	11
40600525	LEVELING BINDER (HAND METHOD), N50	TON	18
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600990	TEMPORARY RAMP	SQ YD	55
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3065
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	47
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	253
42400800	DETECTABLE WARNINGS	SQ FT	166
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	36487
44000600	SIDEWALK REMOVAL	SQ FT	419
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL M0	2
67100100	MOBILIZATION	L SUM	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1

80% FED./20% STATE  
URBAN

SUMMARY OF QUANTITIES			
CODE NO.	ITEM	ROADWAY 0005	
		UNIT	TOTAL QUANTITY
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1623
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	498
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	26438
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3364
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	3634
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2267
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	576
* 70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	179
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	498
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	13219
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	330
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1817
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1191
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	288
* 78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	1352
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	305
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	305
* 88600100	DETECTOR LOOP, TYPE I	FOOT	4146
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1532
X4400500	COMBINATION CURB AND GUTTER REMOVAL (SPECIAL)	FOOT	159
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	554
X6061700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B (SPECIAL)	FOOT	159
Z0026346	NIGHTTIME WORK ZONE LIGHTING	L SUM	1
Z0034105	MATERIAL TRANSFER DEVICE	TON	3065

\*SPECIALTY ITEMS

FILE NAME =	USER NAME = monallysr	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
ct:\pw\work\pvidot\monallysr\d0173848\d366826-ah-t-DETAILS.dgn		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	68	(3)RS-2	LASALLE	22	3
PLOT SCALE = 51.2449' / IN.		CHECKED -	REVISED -		CONTRACT NO. 66A06										
PLOT DATE = Mar 15, 2011 - 10:56:21 AM		DATE -	REVISED -		ILLINOIS FED. AID PROJECT										