

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				STATE FUNDS 100% STATE ROADWAY 0005
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	103	103
42400800	DETECTABLE WARNINGS	SQ FT	8	8
44000600	SIDEWALK REMOVAL	SQ FT	103	103
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	10	10
60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	FOOT	10	10
44200998	CLASS B PATCHES, TYPE III, 12 INCH	SQ YD	25	25
44201000	CLASS B PATCHES, TYPE IV, 12 INCH	SQ YD	181	181
44201298	DOWEL BARS 1 1/4"	EACH	116	116
44213100	PAVEMENT FABRIC	SQ YD	411	411
44213200	SAW CUTS	FOOT	543	543
44213204	TIE BARS 3/4"	EACH	98	98
67100100	MOBILIZATION	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	116	116
* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	20	20
X5011100	FOUNDATION REMOVAL	EACH	1	1

*SPECIALITY ITEMS

FILE NAME =	USER NAME = petelyj	DESIGNED - RQL WOODSHANK	REVISED - -----
or\pwork\pwid\petelyj\0259563\0366835-sht-details.DGN	35-sht-details.DGN	DRAWN - RQL WOODSHANK	REVISED - -----
PLOT SCALE = 100.0000 1 / IN.	CHECKED - -----	DATE - -----	REVISED - -----
PLOT DATE = Apr 07, 2011 - 09:44:37 AM	DATE - -----	REVISED - -----	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: _____ SHEET NO. 1 OF 1 SHEETS STA. _____ TO STA. _____

F.A.P. RTE. 332	SECTION (K,5)1-1	COUNTY KANKAKEE	TOTAL SHEETS 8	SHEET NO. 3
CONTRACT NO. 66B35			ILLINOIS FED. AID PROJECT	

Rev.