

SUMMARY OF QUANTITIES

Specialty_Item	CodeNo	Description	Unit	Total Quantities URBAN	1	2	3	4	5	6	7	8	9
					0014 Tazewell Structure 90/10 FED. STATE	0005 Peoria County 90/10 FED. STATE	0005 Tazewell County 90/10 FED. STATE	0005 Peoria County 100% State	0005 Tazewell County 100% State	0021 Peoria County Homeland Security Funds 100% FED	0021 Tazewell County Homeland Security Funds 100% FED	0021 LIGHTING Peoria County 90/10 FED. STATE	0021 LIGHTING Tazewell County 90/10 FED. STATE
X	81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	4020						1765	2255		
X	81021330	CONDUIT PUSHED, 2" DIA., PVC	FOOT	300						250	50		
X	81100300	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., GALVANIZED STEEL	FOOT	235						140	95		
X	81100400	CONDUIT ATTACHED TO STRUCTURE, 1 1/4" DIA., GALVANIZED STEEL	FOOT	240						160	80		
X	81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	5115						1800	3315		
X	81300948	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 24" X 24" X 10"	EACH	12						5	7		
X	81603030	UNIT DUCT, 600V, 2-1C NO. 4, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	1975						1615			360
X	81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	3270						916	2354		
X	81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	4634						888	3746		
X	81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	3348						944	2404		
X	81800185	AERIAL CABLE, 2-1/C NO. 1/0 WITH MESSENGER WIRE	FOOT	1300								1300	
X	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	10260						1705	2195	6000	360
X	82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	4									4
X	82104000	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 400 WATT	EACH	11								6	5
X	83057012	LIGHT POLE, WOOD, 30 FOOT, CLASS 5	EACH	1								1	
X	83057340	LIGHT POLE, WOOD, 60 FOOT, CLASS 3	EACH	7								6	1
	84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	11								6	5
X	87012400	ELECTRIC CABLE IN TRENCH, 600V (TRIPLEXED) 2-1/2" NO. 4/0 AND 1/C NO. 2/0 GROUND	FOOT	6360								6,000	360
X	87100140	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 12F	FOOT	4802						965	3837		
X	87800310	CONCRETE FOUNDATION, TYPE E 24-INCH DIAMETER (SPECIAL)	FOOT	10						5	5		
X	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	35						15	20		

FILE NAME = Sm.0.dgn	USER NAME = Jobabidism	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
474	(72, 90)5BJI-2	PEO TAZ	179	5
CONTRACT NO. 68069				
ILLINOIS FED. AID PROJECT				