

SUMMARY OF QUANTITIES

Specialty_Item	CodeNo	Description	Unit	Total Quantities URBAN	0014 Tazewell Structure 90/10 FED. STATE	0005 Peoria County 90/10 FED. STATE	0005 Tazewell County 90/10 FED. STATE	0005 Peoria County 100% State	0005 Tazewell County 100% State	0021 Peoria County Homeland Security Funds 100% FED	0021 Tazewell County Homeland Security Funds 100% FED	0021 LIGHTING Peoria County 90/10 FED. STATE	0021 LIGHTING Tazewell County 90/10 FED. STATE
	X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1		0.3	0.7						
	X7040010	TEMPORARY CONCRETE BARRIER (SPECIAL)	FOOT	190		110	80						
X	X7800610	URETHANE PAVEMENT MARKING - LINE 4"	FOOT	44200		21230	22970						
X	X7800630	URETHANE PAVEMENT MARKING - LINE 6"	FOOT	4820		2651	2169						
X	X7800640	URETHANE PAVEMENT MARKING - LINE 8"	FOOT	3190			3190						
X	X7800650	URETHANE PAVEMENT MARKING - LINE 12"	FOOT	195			195						
X	X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	44200		21230	22970						
X	X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	4820		2651	2169						
X	X7830076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	3190			3190						
X	X7830078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	FOOT	195			195						
X	X8040102	ELECTRIC SERVICE INSTALLATION, SPECIAL	EACH	1							1		
X	X8250505	LIGHTING CONTROLLER, SPECIAL	EACH	1								1	
X	X8710030	FIBER OPTIC CABLE 48 FIBERS, SINGLE MODE	FOOT	5254					2448	2806			
X	X8710050	FIBER OPTIC ETHERNET DROP AND REPEAT SWITCH	EACH	4					2	2			
●	Z0076600	TRAINEES	HOUR	1000	1,000								
	Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	24	24								
	Z0001905	STRUCTURAL STEEL REPAIR	POUND	20,500	20,500								
	Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	29,961	29,961								
	Z0006012	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	29520	29520								
	Z0007101	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO.1	L SUM	1	1								
	Z0007102	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO.2	L SUM	1	1								
	Z0012130	BRIDGE DECK SCARIFICATION 3/4"	SQ YD	29,961	29,961								

● 0042