

SUMMARY OF QUANTITIES

Specialty_Item	CodeNo	Description	Unit	Total Quantities URBAN	1	2	3	4	5	6	7	8	9
					0014 Tazewell Structure 90/10 FED. STATE	0005 Peoria County 90/10 FED. STATE	0005 Tazewell County 90/10 FED. STATE	0005 Peoria County 100% State	0005 Tazewell County 100% State	0021 Peoria County Homeland Security Funds 100% FED	0021 Tazewell County Homeland Security Funds 100% FED	0021 LIGHTING Peoria County 90/10 FED. STATE	0021 LIGHTING Tazewell County 90/10 FED. STATE
	Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	2871	2871								
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1		0.55	0.45						
	Z0015802	PLUG EXISTING DECK DRAINS	EACH	1331	1331								
	Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	102	102								
	Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	28	28								
	Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	58.9	58.9								
X	Z0033052	COMMUNICATIONS VAULT	EACH	4						1	3		
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1			1						
	Z0062000	SAW CUTTING	FOOT	3105		1825	1280						
	X5210180	HIGH LOAD MULTI-ROTATIONAL BEARINGS, GUIDED EXPANSION, 650K	EACH	20	20								
	Z0012130	BRIDGE DECK SCARIFICATION 3/4"	SQ YD	29961	29961								
X	87012400	ELECTRIC CABLE IN TRENCH, 600V, (TRIPLEXED) 2-1/0 NO. 4/0 AND 1/2 NO. 2/0 GROUND	FOOT	6360								6000	360
X	83057012	LIGHT POLE, WOOD, 30 FOOT, CLASS 5	EACH	1								1	

FILE NAME = Sm.0.0.dgn	USER NAME = jlababidism	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
474	((72, 90)5B)I-2	PEO TAZ	129	8
CONTRACT NO. 68069				
ILLINOIS FED. AID PROJ. #T				