

TABULATION OF CONCRERTE BARRIER QUANTITIES								
LOCATION			LENGTH	TEMPORARY CONCRETE BARRIER	TEMPORARY CONCRETE BARRIER (RELOCATE)	TEMPORARY CONCRETE BARRIER (SPECIAL) **		
							FT	FT
	STA.	TO	STA.					
STAGE I	Sta 448+20	TO	Sta 449+28	108	108	108		
	Sta 56+07	TO	Sta 101+07	4500	4500	4500		
	TOTAL			4608	4608	4608		
STAGE II	Sta 57+45	TO	Sta 104+07	4662	4662	4662		
	TOTAL			4662				
EAST CROSS OVER	Sta 101+30	TO	Sta 100+50	80				80
WEST CROSS OVER	Sta 58+60	TO	Sta 57+50	110				110
TOTAL				4675	*	4675		190

* USE THE LONGEST OF THE TWO STAGES AND ROUND IT TO THE NEAREST 12.5 SINCE THE BARRIER WALL COMES IN 12.5 FEET SECTIONS
 ** SEE SPECIAL PROVISION AND PLANS FOR MORE DETAIL

TABULATION OF SHOULDER REMOVAL QUANTITIES								
LOCATION			PAVED SHOULDERS REMOVAL (MEASURED AREA)	SAW CUT	SHOULDER RUMBLE STRIP			
					SQFT	SQYD	FT	FT
	STA.	TO	STA.					
EAST OF STRUCTURE	EASTBOUND							
	STA 97+60	TO	STA 100+10	1550	172	250	250	
	STA 101+60	TO	STA 104+10	1485	165	250	250	
	WESTBOUND							
	STA 97+95	TO	STA 100+05	1270	141	210	210	
	STA 101+80	TO	STA 103+50	1005	112	170	170	
	NORTH SHOULDERS							
	STA 97+40	TO	STA 99+65	1822	202	225	225	
	SOUTH SHOULDERS							
	STA 97+45	TO	STA 99+20	1717	191	175	175	
WEST OF STRUCTURE	EASTBOUND							
	STA 448+00	TO	STA 56+97	1275	142	220	220	
	STA 58+96	TO	STA 61+26	1372	152	230	230	
	WESTBOUND							
	STA 448+22	TO	STA 57+23	2287	254	225	225	
	STA 59+10	TO	STA 61+14	1190	132	205	205	
	NORTH SHOULDERS							
	STA 59+50	TO	STA 62+65	3075	342	315	315	
	SOUTH SHOULDERS							
	STA 56+50	TO	STA 62+80	6115	679	630	630	
TOTAL					2690	3105	3105	

TABULATION OF EARTHWORK QUANTITIES				
LOCATION			FURNISHED EXC	TOPSOIL FURNISH & PLACE 4"
			(CU YD)	(SQ YD)
WEST CROSS OVER				1005
STA 448+00	TO	STA 449+00	20	
STA 449+00	TO	STA 57+00	182	
STA 57+00	TO	STA 58+00	150	
STA 58+00	TO	STA 59+00	130	
STA 59+00	TO	STA 60+00	13	
WEST TOTAL			495	1005
EAST CROSS OVER				755
STA 99+00	TO	STA 100+00	135	
STA 100+00	TO	STA 101+00	150	
STA 101+00	TO	STA 102+00	80	
STA 102+00	TO	STA 103+00	5	
EAST TOTAL			370	755
TOTAL			865	1760

FILE NAME = Quantities for Schedule and Summary.dgn	USER NAME = labebidism	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLDT SCALE = 100.0000' / IN.	CHECKED -	REVISED -
	PLDT DATE = 2/9/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	F.A.I. RTE. 474	SECTION ((72, 90)5B)I-2	COUNTY PEO-TAZ	TOTAL SHEETS 129	SHEET NO. 12
						CONTRACT NO. 68069	
ILLINOIS FED. AID PROJECT							