

TABULATION OF LIGHTING QUANTITIES

ITEM DESCRIPTION	UNIT	TOTAL QTY.
UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	360
AERIAL CABLE, 2-1/C NO. 1/0 WITH MESSENGER WIRE	FOOT	1300
ELECTRIC CABLE IN TRENCH, 600V, 2-1/C NO. 4/0 AND 1/C NO. 2/0 GROUND	FOOT	6000
TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	6300
LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 400 WATT	EACH	11
LIGHTING CONTROLLER, SPECIAL	EACH	1
LIGHT POLE, WOOD, 30 FOOT, CLASS 5	EACH	1
LIGHT POLE, WOOD, 60 FOOT, CLASS 3	EACH	7
REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	11
LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT (INSTALL ONLY)	EACH	4

FILE NAME =	USER NAME = lababzian	DESIGNED -	REVISED -
Quantities for Schedule and Summary.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 2/10/2011	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
			129	17
SCALE:			SHEET NO. OF SHEETS STA. TO STA.	
			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 68069	