



**FRAMING PLAN SPAN 16**  
Westbound Lanes

**BILL OF MATERIAL**

Item	Unit	Quantity
Hot-Mix Asphalt Wearing Surface Removal, Deck	Sq. Yc.	712
Bridge Deck Scarification, 3/4"	Sq. Yc.	712
Bridge Deck Latex Concrete Overlay, 2 1/4"	Sq. Yc.	701
Plug Existing Deck Drains	Each	11
Floor Drain Extension	Each	11
Bolt Replacement	Each	1
Structural Steel Repair	Pound	920

**LEGEND**

- ① Plug Existing Floor Drains
- ② Extend Existing Drain
- ⓓ Expansion Joint Trough Installation

FILE NAME =	USER NAME = #USER#	DESIGNED - JAN.	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL PLAN &amp; REPAIR LOCATION WESTBOUND SPAN 16 S.N. 090-0109</b>	F.A.I. RTE.	SECTION	COUNT	TOTAL SHEETS	SHEET NO.
#FILE#		CHECKED - BTO	REVISED -			474		PEORIA & TAYLOR	129	48
	PLOT SCALE = #SCALE#	DRAWN - MJK	REVISED -					CONTRACT NO. 68069		
	PLOT DATE = #DATE#	CHECKED - JAN	REVISED -			SHEET NO. 14 OF 65 SHEETS		ILLINOIS FED. AID PROJ. CT		