

SUMMARY OF QUANTITIES			URBAN	STP	HSIP		CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0004 ROADWAY 80% FED 20% STATE	0004 RDWY 90% FED 10% STATE	0021 SAFETY 100% CITY	0021 SAFETY 90% FED 7.5% STATE 2.5% CITY	0021 SAFETY 90% FED 5.0% STATE 5.0% CITY
56108800	TAPPING VALVES AND SLEEVES 6"	EACH	2	2				
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	3	3				
56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	3	3				
60218300	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2		2			
60218400	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3		3			
60219100	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 9 FRAME AND GRATE	EACH	3		3			
60221100	MANHOLES, TYPE A, 5' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5		5			
60224446	MANHOLES, TYPE A, 7' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		1			
60255500	MANHOLES TO BE ADJUSTED	EACH	6		6			
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	6		6			
60266600	VALVE BOXES TO BE ADJUSTED	EACH	5		5			
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	11		11			
60500040	REMOVING MANHOLES	EACH	8		8			
60500060	REMOVING INLETS	EACH	18		18			
60600605	CONCRETE CURB, TYPE B	FOOT	435	435				
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2901		2901			
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1,012	1,012				
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1				
66900530	SOIL DISPOSAL ANALYSIS	EACH	0					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9				
67100100	MOBILIZATION	L SUM	1	1				
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	180	180				
70300100	SHORT TERM PAVEMENT MARKING	FOOT	11735	11735				
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	23	23				

1

REVISED 6-9-11

FILE NAME D468877-CA00.dgn	USER NAME = bergsteker	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES LOCUST STREET-RECONSTRUCTION	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 100.0000' / IN.	DRAWN -	REVISED -			685/22	(412, 135) R.N. (ICS) 1	FULTON	125	6A
	PLOT DATE = 1/3/2011	CHECKED -	REVISED -			CONTRACT NO. 68877				
		DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT D4-94-009-09				