

SUMMARY OF QUANTITIES			URBAN	STP	HSIP		CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0004 ROADWAY 80% FED 20% STATE	0004 RDWY 90% FED 10% STATE	0021 SAFETY 100% CITY	0021 SAFETY 90% FED 7.5% STATE 2.5% CITY	0021 SAFETY 90% FED 5.0% STATE 5.0% CITY
20200100	EARTH EXCAVATION	CU YD	2892	2892				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	289	289				
20800150	TRENCH BACKFILL	CU YD	883	883				
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SO YD	8898	8898				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	1172	1172				
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	15	15				
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	15	15				
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	15	15				
* 25200100	SODDING	SO YD	1172	1172				
28000400	PERIMETER EROSION BARRIER	FOOT	284	284				
28000500	INLET AND PIPE PROTECTION	EACH	43	43				
31100910	SUB BASE GRANULAR MATERIAL, TYPE A 12"	SO YD	7684		7684			
31102000	SUB BASE GRANULAR MATERIAL, TYPE C	CU YD	289	289				
31200100	STABILIZED SUB BASE 4"	SO YD	1136	1136				
35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SO YD	609	609				
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SO YD	523	523				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4528	4528				
40600300	AGGREGATE (PRIME COAT)	TON	26	26				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1333	1333				
40603230	POLYMERIZED HOT - MIX ASPHALT BINDER COURSE, IL - 19.0, N50	TON	98	98				
40603335	HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1026	1026				
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SO YD	6229		6229			
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	816		816			
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SO FT	19293		19293			

*SPECIALTY ITEMS

FILE NAME D468877-CADD.dgn	USER NAME = bergasokere	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 1/3/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
LOCUST STREET-RECONSTRUCTION

F.A.P. RTE. 585/22	SECTION (412, 135) R.N. (LCS) 1	COUNTY FULTON	TOTAL SHEETS 125	SHEET NO. 5
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 68877	
04-94-009-09				