

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN	STP	HSIP		CONSTRUCTION TYPE CODE	
				0004 ROADWAY 80% FED 20% STATE	0004 RDWY 90% FED 10% STATE	0021 SAFETY 100% CITY	0021 SAFETY 90% FED 7.5% STATE 2.5% CITY	0021 SAFETY 90% FED 5.0% STATE 5.0% CITY	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	14930	14930					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	485	485					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	9881	9881					
72000100	SIGN PANEL - TYPE 1	SQ FT	94	94					
72000200	SIGN PANEL - TYPE 2	SQ FT	30	30					
72300100	INSTALL EXISTING SIGN PANEL	SQ FT	127	127					
72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	65	65					
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	37	37					
72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	2	2					
72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	83	83					
72900100	METAL POST - TYPE A	FOOT	171	171					
72900200	METAL POST - TYPE B	FOOT	361	361					
• 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	734	734					
• 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4929	4929					
• 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	2671	2671					
• 78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	485	485					
• 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	247	247					
• 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	128	128					
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	262	262					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1760	1760					
• 80500200	SERVICE INSTALLATION, TYPE B	EACH	3				1	2	
• 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	1472				662	810	
• 81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	22					22	
• 81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	81				33	48	

\*SPECIALTY ITEMS

FILE NAME D468877-CADD.dgn	USER NAME = bergstakerec	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 1/4 IN.	CHECKED -	REVISED -
	PLOT DATE = 1/3/2011	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
LOCUST STREET-RECONSTRUCTION

F.A.P. RTE. 685/22	SECTION (412, 135) R.N. (ICS) 1	COUNTY FULTON	TOTAL SHEETS 125	SHEET NO. 68
CONTRACT NO. 68877				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT D4-94-009-09				