

SUMMARY OF QUANTITIES--CONTINUED

Specialty Item	Code No.	Description	Unit	URBAN Total Qty.	SFTY. US 150 PEORIA CTY. 90%FED 10%STA. 0004	0021 US 150 LIGHTING 90% FEDERAL 10% STATE
	70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1	
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	8	8	
*	78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	31	31	
*	78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	80	80	
*	78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	851	851	
*	78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	612	612	
*	78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	292	292	
*	78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	49	49	
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	8	8	
	78300100	PAVEMENT MARKING REMOVAL POLYETHYLENE	SQ FT	513	513	
	81603035	UNIT DUCT, 600V, 2-1C NO. 6, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1" DIA.	FOOT	475		475
	81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	375		375
	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	475		475
	83800650	BREAKAWAY DEVICE, COUPLING WITH STAINLESS STEEL SCREEN	EACH	12		12
	X5510100	STORM SEWER REMOVAL	FOOT	40	40	
	X6640300	CHAIN LINK FENCE REMOVAL	FOOT	40	40	
	X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1	
	X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	45	45	
	X8440110	RELOCATE EXISTING LIGHT POLE WITH LUMINAIRE	EACH	3	3	
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
	Z0030030	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1	
	X6021065	INLETS, TYPE G-1, SPECIAL	EACH	1	1	
	40603214	POLYMERIZED HOT - MIX ASPHALT BINDER COURSE, IL - 12.5, N70	TON	47	47	

*SPECIALTY ITEM