

MOBILIZATION	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

CHAIN LINK FENCE REMOVAL	
LOCATION	FOOT
HARVARD AVE.	40
TOTAL	40

REMOVING INLETS	
LOCATION	EACH
RT. STA. 192+00	1
TOTAL	1

TRAFFIC CONTROL AND PROTECTION STANDARD 701602	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

GUARDRAIL REMOVAL	
LOCATION	FOOT
HARVARD AVE.	25
STA. 187+62-188+00	38
TOTAL	63

STORM SEWER REMOVAL	
LOCATION	FOOT
RT. STA. 192+00	40
TOTAL	40

TRAFFIC CONTROL AND PROTECTION STANDARD (SPECIAL)	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

MEDIAN REMOVAL	
LOCATION	SQ FT
RAMPS A&B STA. 7+51- 8+31	1023
TOTAL	1023

PAVEMENT MARKING REMOVAL	
LOCATION	SQ FT
RAMP A	60
RAMP B	189
RAMP C	264
TOTAL	513

TRAFFIC CONTROL SURVEILLANCE	
LOCATION	CAL DAY
JOBSITE	8
TOTAL	8

PAVEMENT REMOVAL	
LOCATION	SQ. YD
RT. STA. 192+51-193+00	64
TOTAL	64

RELOCATE EXISTING LIGHT POLE WITH LUMINAIRE	
LOCATION	EACH
RT. STA. 191+70	1
LT. STA. 7+90 (RAMP A)	1
RT. STA. 189+75	1
TOTAL	3

CHANGEABLE MESSAGE SIGN	
LOCATION	CAL DAY
JOBSITE	45
TOTAL	45

COMBINATION CURB AND GUTTER REMOVAL	
LOCATION	FOOT
RT. STA. 189+62-7+55 (RAMP A)	339
TOTAL	339

3 SIGNS @ 15 DAYS EACH

CONSTRUCTION LAYOUT	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

GUTTER REMOVAL	
LOCATION	FOOT
LT. STA. 7+25-7+54 (RAMP A)	29
TOTAL	29

ENGINEER'S FIELD OFFICE TYPE A	
LOCATION	CAL MO
JOBSITE	1
TOTAL	1

PAVED SHOULDER REMOVAL	
LOCATION	SQ YD
RAMP A LT. STA. 7+25	18
TOTAL	18

FILE NAME = D468992-eh-t-plnprf.dgn

USER NAME = longer

DESIGNED - ---

REVISED - ---

DRAWN - ---

REVISED - ---

PLOT SCALE = 40.0016 "/ IN.

CHECKED - ---

REVISED - ---

PLOT DATE = 3/24/2011

DATE - ---

REVISED - ---

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	14R	PEORIA	42	7
			CONTRACT NO. 68992	

SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____

ILLINOIS FED. AID PROJECT