

SCHEDULE OF RESURFACING AND NEW PAVEMENT QUANTITIES									
LOCATION	HMA SURFACE REM. BUTT JT. SQ. YD.	HMA SURFACE REM. 3 1/2" SQ. YD.	TEMPORARY RAMP SQ. YD.	POLY. BIT. MATL. PRIME COAT TON	POLY. BINDER CSE. N70 TON	POLY. HMA. SURF. CSE. MIX E N70 TON	PCC PVT. 9.5" SQ. YD.	PCC BASE. CSE. 10" SQ. YD.	PAVEMENT FABRIC SQ. YD.
RT. STA. 189+62-192+15	79	234	33	1	47	35		117	
RAMP B RT. STA. 7+51-8+43							111		111
TOTAL	79	234	33	1	47	35	111	117	111

STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	
LOCATION	FOOT
HARVARD AVE.	25
TOTAL	25

CHAIN LINK FENCE, 4'	
LOCATION	FOOT
HARVARD AVE.	30
TOTAL	30

IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	
LOCATION	EACH
STA. 187+62-188+00	1
TOTAL	1

EARTH EXCAVATION	
LOCATION	CU. YD.
RT. STA. 189+62-192+15	208.1
RAMP A RT. STA. 7+25-8+43	122.4
TOTAL	331

SUB-BASE GRANULAR MATERIAL TYPE B	
LOCATION	TON
RT. STA. 189+62-192+15	95.3
RAMP A RT. STA. 7+25-8+43	49.2
TOTAL	145

EPOXY PAVEMENT MARKINGS						
LOCATION	LINE 4" YELLOW	LINE 6" WHITE	LINE 8" WHITE	LINE 12" WHITE	LINE 24" WHITE	LETTERS & SYMBOLS
	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT
RAMP A & (ML)TURN LANE	40		532	22		31.2
RAMP B	40	261	80	87	24	
RAMP C		590		183	25	
TOTAL	80	851	612	292	49	31.2

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	
LOCATION	FOOT
RT. STA. 189+62(ML)-7+55(RAMP A)	359
TOTAL	359

CONCRETE MEDIAN, TYPE SM-4.24	
LOCATION	SQ FT
RAMP A&B STA. 7+51- 8+43	1174
TOTAL	1174

RAISED REFLECTIVE PAVEMENT MARKER	
LOCATION	EACH
RT. STA. 190+05-191+87	8
TOTAL	8