

MATCH STA. 191+29

RELOC EX LT UNIT SPL
1.0 EACH
(INSTALL 5 FT. BEHIND
EDGE OF CURB -LOCATION
AS APPROVED BY THE
ENGINEER)

BKWY DEV COU SS SCR
4.0 EACH

UD 2#6 #6G XLP USE 1
90.0 FT.
(INSTALL TO LIGHTING
UNIT #19)

EXTEND EXISTING 2" GSC
CONDUIT AND UNIT DUCT
TO RELOCATED LIGHT POLE
(DISTANCE AS REQUIRED -
WORK INCLUDED IN COST OF
UD 2#6 #6G XLP USE 1)

EQ C XLP USE 1C 6
125.0 FT. X 3


RELOC EX LT UNIT SPL
1.0 EACH
(INSTALL 5 FT. BEHIND
EDGE OF CURB -LOCATION
AS APPROVED BY THE
ENGINEER)

BKWY DEV COU SS SCR
4.0 EACH

REMOVE ELECTRIC CABLES
FROM EX. UNIT DUCT AND
INSTALL 2 1/C #6 CABLES
FROM LIGHT POLE #18 TO #19
(COST OF REMOVAL INCLUDED
IN BID PRICE FOR ELECTRICAL
CABLE)

PROJECT ENDS
STA. 195+01

ITEM DESCRIPTION	UNIT	QUANTITY
UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	90
ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6 FOOT EC C XLP USE 1C 6	FOOT	375
TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	90
BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	8
RELOCATE EXISTING LIGHTING UNIT, SPECIAL	EACH	2



FILE NAME = 68992 - Overhead Lighting.dgn	USER NAME = hoveider	DESIGNED - ---	REVISED - ---
		DRAWN - ---	REVISED - ---
		CHECKED - ---	REVISED - ---
		DATE - ---	REVISED - ---

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**US 150 (WAR MEMORIAL DR.) & IL 29 (ADAMS ST.)
PROPOSED LIGHT POLE RELOCATION DETAILS**

SCALE: _____ SHEET NO. ____ OF ____ SHEETS STA. _____ TO STA. _____

F.A.P. RTE. 317	SECTION 14R	COUNTY PEORIA	TOTAL SHEETS 42	SHEET NO. 22
CONTRACT NO. 68992			ILLINOIS FED. AID PROJECT	