

TABULATION OF RESURFACING QUANTITIES

| LOCATION | TOTAL ROADWAY WIDTH | LENGTH | AREA | BITUMINOUS SURFACE REMOVAL BUTT JOINT | TEMPORARY RAMP | BITUMINOUS SURFACE REMOVAL 2" | POLY BIT MATERIALS PRIME COAT | AGGREGATE MATERIALS PRIME COAT | INCIDENTAL SURF CSE MIX C N50 | POLY HMA SURF CSE MIX E N50 | MATERIAL TRANSFER DEVICE |
|-----------------------------------|---------------------|---------|---------|---------------------------------------|----------------|-------------------------------|-------------------------------|--------------------------------|-------------------------------|-----------------------------|--------------------------|
| | FT | FT | SQ YD | SQ YD | SQ YD | SQ YD | TON | TON | TON | TON | TON |
| STA. 282 + 63 TO 282 + 93 | 36.00 | 30.00 | 120.00 | 120.00 | 20.00 | | 0.04 | 0.24 | | 13.44 | 13.44 |
| STA. 282 + 93 TO 290 + 00 | 36.00 | 707.00 | 2828.00 | | | 2828.00 | 1.00 | 5.65 | | 316.76 | 316.76 |
| STA. 290 + 00 TO 290 + 80 | 36.50 | 80.00 | 324.44 | | | 324.44 | 0.11 | 0.64 | | 36.33 | 36.33 |
| Intersection of Main & Sycamore * | | | 726.52 | | | 726.52 | 0.24 | 1.45 | | 81.37 | 81.37 |
| STA. 291 + 66 TO 293 + 47 | 71.10 | 181.00 | 1429.90 | | | 1429.90 | 0.48 | 2.86 | | 160.14 | 160.14 |
| STA. 293 + 47 TO 312 + 27 | 35.50 | 1880.00 | 7415.55 | | | 7415.55 | 2.52 | 14.83 | | 830.54 | 830.54 |
| STA. 312 + 27 TO 312 + 57 | 36.00 | 30.00 | 120.00 | 120.00 | 20.00 | | 0.04 | 0.24 | | 13.44 | 13.44 |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| East Sycamore Street | 60.00 | 30.00 | 200.00 | 200.00 | 22.77 | | 0.06 | 0.40 | 22.40 | | |
| West Sycamore Street | 62.00 | 20.00 | 137.77 | 137.77 | 21.11 | | 0.04 | 0.27 | 15.43 | | |
| West Birch Street | 45.00 | 23.00 | 115.00 | 115.00 | 15.55 | | 0.04 | 0.23 | 12.88 | | |
| East Birch Street | 46.50 | 23.00 | 118.83 | 118.83 | 16.11 | | 0.04 | 0.23 | 13.30 | | |
| West Myrtle Street | 41.50 | 23.00 | 106.05 | 106.05 | 15.55 | | 0.03 | 0.21 | 11.87 | | |
| East Vine Street | 49.00 | 18.00 | 98.00 | 98.00 | 18.88 | | 0.03 | 0.20 | 11.00 | | |
| West Vine Street | 48.00 | 16.00 | 85.33 | 85.33 | 16.11 | | 0.03 | 0.17 | 9.55 | | |
| East Olive Street | 43.00 | 16.00 | 76.44 | 76.44 | 16.66 | | 0.02 | 0.15 | 8.56 | | |
| West Olive Street | 43.00 | 23.00 | 109.88 | 109.88 | 15.55 | | 0.03 | 0.22 | 12.30 | | |
| West Ash Street | 43.50 | 26.00 | 125.66 | 125.66 | 15.00 | | 0.04 | 0.25 | 14.07 | | |
| | | | | | | | | | | | |
| GRAND-TOTAL | | | | 1,413 | 213 | 12,724 | 4.8 | 28.2 | 131 | 1,452 | 1,452 |

| | | |
|----------------------------|----------------|-----------------|
| USER NAME = appenzeller.jj | DESIGNED - --- | REVISED - ----- |
| PLOT SCALE = 1/8" = 1' IN. | DRAWN - --- | REVISED - ----- |
| PLOT DATE = 3/22/2011 | CHECKED - --- | REVISED - ----- |
| | DATE - ----- | REVISED - ----- |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

| SCHEDULE OF QUANTITIES | | | |
|------------------------|-------------------------------|--------------------------|--|
| SCALE: _____ | SHEET NO. ____ OF ____ SHEETS | STA. _____ TO STA. _____ | |

| | | | | |
|---------------------------|-----------------|---------------|-----------------|--------------|
| F.A.P. RTE. 22 | SECTION 135RS-7 | COUNTY FULTON | TOTAL SHEETS 29 | SHEET NO. 19 |
| CONTRACT NO. 68978 | | | | |
| ILLINOIS FED. AID PROJECT | | | | |