

INDEX OF SHEETS

1	COVER SHEET
2 - 3	LOCATION MAP
4	INDEX OF SHEETS, HIGHWAY STANDARDS, & GENERAL NOTES
5	SUMMARY OF QUANTITIES
6 - 10	LOCATION 1 - MATTIS AVE.
11 - 13	LOCATION 2 - PROSPECT AVE.
14 - 18	LOCATION 3 - SPRINGFIELD AVE. & WRIGHT ST.
19 - 23	LOCATION 4 - CUNNINGHAM AVE. & UNIVERSITY AVE.
24 - 34	LOCATION 5 - US RTE 45

GENERAL NOTES

G.N. - 100 ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

G.N.-105.07 EXISTING STATE-OWNED AND MAINTAINED UTILITY LINES ARE SHOWN ON THE PLANS TO INDICATE THEIR PRESENCE AND APPROXIMATE LOCATION. THE CONTRACTOR SHALL NOTIFY THE DISTRICT OPERATIONS ENGINEER TWO WEEKS PRIOR TO COMMENCING ANY EXCAVATION IN THE VICINITY OF THESE LINES. THE STATE WILL THEN LOCATE AND MARK THE HORIZONTAL LOCATIONS OF THE LINES AND PROVIDE ANY AVAILABLE INFORMATION AS TO THEIR DEPTH. SHOULD ANY OF THE LINES BE DAMAGED BY THE CONTRACTOR'S OPERATION, THE CONTRACTOR SHALL REPAIR THEM TO THE SATISFACTION OF THE ENGINEER AND AT NO COST TO THE STATE.

ALSO THERE MAY BE UTILITIES PRESENT WHICH WERE INSTALLED BY THE STATE BUT ARE MAINTAINED BY OTHERS (CITY, TOWN, ETC.) THE APPROXIMATE LOCATIONS OF THESE LINES ARE ALSO SHOWN ON THE PLANS ALONG WITH THE NAME OF THE MAINTAINING AGENCY. THE CONTRACTOR SHALL COORDINATE THE LOCATING OF THESE LINES WITH THE LOCAL AGENCY PRIOR TO COMMENCING ANY EXCAVATION OR BORING IN THEIR VICINITY. SHOULD THESE LINES BE DAMAGED BY THE CONTRACTOR'S OPERATIONS, THE CONTRACTOR SHALL REPAIR THEM TO THE SATISFACTION OF, AND AT NO COST TO, THE LOCAL AGENCY AND THE STATE.

HIGHWAY STANDARDS

<u>Standard</u>	<u>Description</u>
000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001006	DECIMAL OF AN INCH AND OF A FOOT
701006-03	OFF-ROAD OPERATIONS, 2L 2W 15' (4.5M) TO 24" (600MM) FROM PAVEMENT EDGE.
701101-02	OFF-ROAD OPERATIONS, MULTILANE, 15' (4.5M) TO 24" (600 MM) FROM PAVEMENT EDGE
701201-04	URBAN LANE CLOSURE, 2L 2W UNDIVIDED
701406-06	LANE CLOSURE, MULTILANE, DAY OPERATIONS ONLY, SPEEDS > 45 MPH TO 55 MPH
701602-05	URBAN LANE CLOSURE, MULTILANE, 2W WITH BIDIRECTIONAL LEFT TURN LANE
701606-07	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
701701-07	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801-04	LANE CLOSURE, MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
701901-01	TRAFFIC CONTROL DEVICES
814001-02	HANDHOLES
857001-01	STD PHASE DESIGNATION DIAGRAMS & PHASE SEQUENCE
878001-08	CONCRETE FOUNDATION DETAILS

701421-03

FILE NAME =	USER NAME = bucklesJJ	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, HIGHWAY STANDARDS & GENERAL NOTES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ci:\pwwork\pwwork\bucklesJJ\d0261322\0570911-sht-Cover.dgn	0911-sht-Cover.dgn	DRAWN -	REVISED -			VAR.	FY2011 INTERCONNECT	Champaign	34	4	
PLOT SCALE = 40,0000' / IN.	CHECKED -	REVISIED -				CONTRACT NO. 70911					
PLOT DATE = 3/25/2011	DATE -	REVISED -				[ILLINOIS] FED. AID PROJECT					
				SCALE:		SHEET NO. OF SHEETS STA. TO STA.					