

LOCATION OF WORK:	LOCATION #1	LOCATION #2	LOCATION #3	LOCATION #4	LOCATION #5
	FAP 811 (MATTIS AVE)	FAP 804 (PROSPECT AVE)	FAP 808 (SPRINGFIELD AVE & WRIGHT ST)	FAP 800 (CUNNINGHAM AVE) & FAP 808 (UNIVERSTIY AVE)	FAP 804 (US RTE 45)
	BLOOMINGTON RD TO SPRINGER DR	BLOOMINGTON RD TO SPRINGFIELD AVE	STATE ST TO UNIVERSITY AVE	KERR AVE TO WRIGHT ST.	SPRINGFILED AVE TO MONTICELLO RD
	CHAMPAIGN CO 100 % STATE 0021	CHAMPAIGN CO 100 % STATE 0021	CHAMPAIGN CO 100 % STATE 0021	CHAMPAIGN CO 100 % STATE 0021	CHAMPAIGN CO 100 % STATE 0021

URBAN  
CONSTRUCTION TYPE CODE:

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1371	181	242	202	302	444
44000600	SIDEWALK REMOVAL	SQ FT	1700	225	300	250	375	550
67100100	MOBILIZATION	L SUM	1	0.11	0.12	0.15	0.49	0.13
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	8561	8				8553
81021330	CONDUIT PUSHED, 2" DIA., PVC	FOOT	54390	8384	5711	5865	7235	27195
81300720	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16" X 12" X 8"	EACH	2	1	1			
81400100	HANDHOLE	EACH	95	14	11	10	14	46
81500130	GULFBOX JUNCTION REMOVAL	EACH	2				2	
81702100	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 12	FOOT	53724	7512	1265	5200	8124	31623
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	8561	8				8553
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	6			2	2	2
85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1	1				
86400100	TRANSCEIVER - FIBER OPTIC	EACH	35	5	1	7	9	13
87100020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	56758	8122	1304	5682	8573	33077
87900100	DRILL EXISTING FOUNDATION	EACH	1	1				
87900200	DRILL EXISTING HANDHOLE	EACH	53	9	4	14	13	13
88500100	INDUCTIVE LOOP DETECTOR	EACH	73	20		16	19	18
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	7	4	2		1	
89502220	MODIFY EXISTING CONCRETE FOUNDATION	EACH	6			2	2	2
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	4758			87	1143	3528
X0326955	REMOVE AND RELOCATE EXISTING ELECTRICAL SERVICE	EACH	5			2	1	2
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.11	0.12	0.15	0.49	0.13
X8050115	SERVICE INSTALLATION, TYPE A (MODIFIED)	EACH	2	1			1	
XX008483	RELOCATE EXISTING UPS BATTERY BACK UP SYSTEM	EACH	2	1				1
X8950105	REMOVE EXISTING TRAFFIC CONTROLLER AND CABINET	EACH	7	1		2	2	2

FILE NAME *	USER NAME *	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pw_vork\pwwdot1\bucklesj\0261322\0570911-sht-500.dgn		DRAWN -	REVISED -						VAR.	FY2011 INTERCONNECT	Champaign	34	5
PLOT SCALE = 40.0000' / 1" IN.		CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 70911				
PLOT DATE = 3/25/2011		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								