

BILL OF MATERIALS
PROSPECT AVE
BLOOMINGTON RD TO SPRINGFIELD AVE

<u>ITEM</u>	<u>UNIT</u>	<u>QUANTITY</u>
CONDUIT PUSHED, 2" DIA., PVC	FOOT	5711
JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16"X12"X8"	EACH	1
HANDHOLE	EACH	11
ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 12	FOOT	1265
TRANSCEIVER - FIBER OPTIC	EACH	1
FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	1304
DRILL EXISTING HANDHOLE	EACH	4
MODIFY EXISTING CONTROLLER CABINET	EACH	2

FILE NAME =	USER NAME = biggsrd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PROSPECT AVE. BILL OF MATERIALS	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\biggsrd\0261372\0570	11-sht-Prospect_Details.dgn	DRAWN -	REVISED -			VAR.	FY2011 INTERCONNECT	Champaign	34	13
	PLOT SCALE = 42.5637' / in.	CHECKED -	REVISED -			CONTRACT NO. 70911				
	PLOT DATE = 4/12/2011	DATE -	REVISED -			SCALE:	SHEET NO. OF	SHEETS	STA.	TO STA.