

**BILL OF MATERIALS**  
**SPRINGFIELD AVE – STATE ST. TO WRIGHT ST**  
**WRIGHT ST. – SPRINGFIELD AVE TO UNIVERSITY AVE**

<u>ITEM</u>	<u>UNIT</u>	<u>QUANTITY</u>
CONDUIT PUSHED, 2" DIA., PVC	FOOT	5865
HANDHOLE	EACH	10
ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 12	FOOT	5200
FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	2
TRANSCIVER - FIBER OPTIC	EACH	7
FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	5682
DRILL EXISTING HANDHOLE	EACH	14
INDUCTIVE LOOP DETECTOR	EACH	16
MODIFY EXISTING CONCRETE FOUNDATION	EACH	2
REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	87
REMOVE AND RELOCATE EXISTING ELECTRICAL SERVICE	EACH	2
REMOVE EXISTING TRAFFIC CONTROLLER AND CABINET	EACH	2

FILE NAME =	USER NAME = biggard	DESIGNED -	REVISED -
ar\pw_work\pwidot\biggard\d0261373\0570	11-shr-Springfield_Interconnect.dgn	DRAWN -	REVISED -
	PLOT SCALE = 48.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/5/2011	DATE -	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**SPRINGFIELD AVE /WRIGHT ST**  
**BILL OF MATERIALS**

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	FY2011 INTERCONNECT	Champaign	34	17
CONTRACT NO. 70911			ILLINOIS FED. AID PROJECT	

SCALE: SHEET NO. OF SHEETS STA. TO STA.