

| CODE NO | ITEM | UNIT | TOTAL QUANTITY FAI 74- RURAL 90% FED 10% STATE 0021 |
|---------------------|------------------------------------------------------------------|-----------------|-----------------------------------------------------------------|
| 20200100 | EARTH EXCAVATION | CU YD | 4,200.00 |
| 20400800 | FURNISHED EXCAVATION | CU YD | 26,750.0 |
| 25000210 | SEEDING, CLASS 2A | ACRE | 36.5 |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 3,300.0 |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 3,300.0 |
| 25000800 | POTASSIUM FERTILIZER NUTRIENT | POUND | 3,300.0 |
| 25100115 | MULCH, METHOD 2 | ACRE | 36.5 |
| 25100630 | EROSION CONTROL BLANKET | SQ YD | 312.0 |
| 28000250 | TEMPORARY EROSION CONTROL SEEDING | POUND | 3,650.0 |
| 28000305 | TEMPORARY DITCH CHECKS | FOOT | 1,664.0 |
| 28000500 | INLET AND PIPE PROTECTION | EACH | 36.0 |
| 28100201 | STONE RIPRAP, CLASS A1 | TON | 12.0 |
| 48101200 | AGGREGATE SHOULDERS, TYPE B | TON | 13,490.0 |
| 50104400 | CONCRETE HEADWALL REMOVAL | EACH | 91.0 |
| 54210580 | REINFORCED CONCRETE PIPE TEE, 30" PIPE WITH 18" RISER | EACH | 4.0 |
| 54217680 | REINFORCED CONCRETE PIPE TEE, 24" PIPE WITH 24" RISER | EACH | 2.0 |
| 54217690 | REINFORCED CONCRETE PIPE TEE, 30" PIPE WITH 24" RISER | EACH | 4.0 |
| 54217700 | REINFORCED CONCRETE PIPE TEE, 30" PIPE WITH 24" RISER | EACH | 4.0 |
| 54244405 | FLUSH INLET BOX FOR MEDIAN, STANDARD 542546 | EACH | 11.0 |
| 54245205 | INLET BOX, STANDARD 542511 | EACH | 8.0 |
| 54246405 | INLET BOX, STANDARD 542531 | EACH | 4.0 |
| 54248510 | CONCRETE COLLAR | CU YD | 30.0 |
| 542A0229 | PIPE CULVERTS, CLASS A, TYPE 124" | FOOT | 166.0 |
| 542A0235 | PIPE CULVERTS, CLASS A, TYPE 130" | FOOT | 8.0 |
| 542A0241 | PIPE CULVERTS, CLASS A, TYPE 136" | FOOT | 24.0 |
| 5420220 | PIPE CULVERTS, CLASS D, TYPE 1, 15" | FOOT | 55.0 |
| 60100060 | CONCRETE HEADWALLS FOR PIPE DRAINS | EACH | 85.0 |
| 60108100 | PIPE UNDERDRAINS 4" (SPECIAL) | FOOT | 611.0 |
| 60218400 | MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH | 1.0 |
| 60221100 | MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH | 3.0 |
| 67000500 | ENGINEER'S FIELD OFFICE, TYPE B | CAL MO | 14.0 |
| 67100100 | MOBILIZATION | L SUM | 1.0 |
| 70100700 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701406 | L SUM | 1.0 |
| 70103815 | TRAFFIC CONTROL SURVEILLANCE | CAL DA | 100.0 |
| X0323583 | SPEED INDICATOR SIGN | CAL DA | 100.0 |
| X0325588 | HIGH TENSION CABLE MEDIAN BARRIER DEMONSTRATION | L SUM | 1.0 |
| X0325667 | WEED CONTROL MOWING STRIP (SPECIAL) | SQ YD | 14,656.0 |
| X0484300 | MEDIAN INLET BOX REMOVAL | EACH | 21.0 |
| X0931400 | INLET BOXES TO BE ADJUSTED (SPECIAL) | EACH | 2.0 |
| X6340205 | GUARD POSTS REMOVAL | EACH | 51.0 |

* SPECIALTY ITEM

| CODE NO | ITEM | UNIT | TOTAL QUANTITY FAI 74- RURAL 90% FED 10% STATE 0021 |
|----------|---------------------------------------------|--------|-----------------------------------------------------------------|
| X7015005 | CHANGEABLE MESSAGE SIGN | CAL DA | 28.0 |
| XZ193300 | SURVEY MARKER, TYPE 1(SPECIAL) | EACH | 2.0 |
| Z0029652 | HIGH TENSION CABLE MEDIAN BARRIER | FOOT | 31,187.0 |
| Z0029654 | HIGH TENSION CABLE MEDIAN BARRIER TERMINALS | EACH | 26.0 |
| Z0076870 | UNDERDRAIN CONNECTION TO STRUCTURE | EACH | 4.0 |

| | | | |
|----------------------------------------------------|--------------------|------------|-----------|
| FILE NAME = | USER NAME = keysrb | DESIGNED - | REVISED - |
| c:\pwork\pwork\keysrb\d0261049\0578927\sh1-500.dgn | | DRAWN - | REVISED - |
| PLOT SCALE = 100.0000' / IN. | | CHECKED - | REVISED - |
| PLOT DATE = 3/25/2011 | | DATE - | REVISED - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------------|-------------|--------|-----------------|--------------|
| 74 | FY11 HSIP-5 | MCLEAN | 101 | 3 |
| CONTRACT NO. 70927 | | | | |
| ILLINOIS FED. AID PROJECT | | | | |