

## SCHEDULE OF QUANTITIES

CLASS A PATCH 10" I 39 MAINLINE NORTHBOUND											
STATION	LOCATION	LANE	LENGTH	WIDTH	TYPE I	TYPE II	TYPE III	TYPE IV	SAWCUTS	TIE BARS 3/4"	PATCHING REINFORCEMENT
			(FT)	(FT)	44200549 (SQ. YD.)	44200553 (SQ. YD.)	44200557 (SQ. YD.)	44200559 (SQ. YD.)	44213200 (FT)	44213204 (EACH)	44213000 (SQ. YD.)
239+30	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
256+50	I-39 MAINLINE (RURAL)	NBDL	10.0	12.0		13.3			78.0		13.3
260+00	I-39 MAINLINE (RURAL)	NBDL	12.0	12.0			16.0		84.0		16.0
260+40	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
264+00	I-39 MAINLINE (RURAL)	NBDL	75.0	6.0				50.0	249.0	75.0	50.0
274+00	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
284+70	I-39 MAINLINE (RURAL)	NBDL	10.0	12.0		13.3			78.0		13.3
328+60	I-39 MAINLINE (RURAL)	NBDL	8.0	12.0		10.7			72.0		10.7
338+50	I-39 MAINLINE (RURAL)	NBDL	12.0	12.0			16.0		84.0		16.0
357+30	I-39 MAINLINE (RURAL)	NBDL	8.0	12.0		10.7			72.0		10.7
358+30	I-39 MAINLINE (RURAL)	NBDL	6.0	12.0		8.0			66.0		8.0
361+50	I-39 MAINLINE (RURAL)	NBDL	12.0	12.0			16.0		84.0		16.0
366+22	I-39 MAINLINE (RURAL)	NBDL	10.0	12.0		13.3			78.0		13.3
379+50	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
NORTHBOUND SUBTOTALS OF CLASS A PATCH, 10 INCH					16.0	69.3	48.0	50.0	1113.0	75.0	183.3

CLASS A PATCH 10" I 39 MAINLINE SOUTHBOUND											
STATION	LOCATION	LANE	LENGTH	WIDTH	TYPE I	TYPE II	TYPE III	TYPE IV	SAWCUTS	TIE BARS 3/4"	PATCHING REINFORCEMENT
			(FT)	(FT)	44200549 (SQ. YD.)	44200553 (SQ. YD.)	44200557 (SQ. YD.)	44200559 (SQ. YD.)	44213200 (FT)	44213204 (EACH)	44213000 (SQ. YD.)
239+80	I-39 MAINLINE (RURAL)	SBDL	60.0	6.0				40.0	204.0	60.0	40.0
242+80	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
254+30	I-39 MAINLINE (RURAL)	SBDL	12.0	7.0		9.3			64.0		9.3
280+10	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
295+00	I-39 MAINLINE (RURAL)	SBDL	30.0	6.0			20.0		114.0	30.0	20.0
297+50	I-39 MAINLINE (RURAL)	SBDL	10.0	6.0		6.7			54.0		6.7
300+25	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
331+50	I-39 MAINLINE (RURAL)	SBDL	10.0	12.0		13.3			78.0		13.3
339+00	I-39 MAINLINE (RURAL)	SBDL	12.0	12.0			16.0		84.0		16.0
352+50	I-39 MAINLINE (RURAL)	SBDL	20.0	6.0		13.3			84.0	20.0	13.3
363+50	I-39 MAINLINE (RURAL)	SBDL	10.0	12.0		13.3			78.0		13.3
375+65	I-39 MAINLINE (RURAL)	SBDL	15.0	12.0			20.0		93.0		20.0
384+75	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
385+20	I-39 MAINLINE (RURAL)	SBDL	10.0	12.0		13.3			78.0		13.3
471+75	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
509+80	I-39 MAINLINE (RURAL)	SBDL	10.0	12.0		13.3			78.0		13.3
SOUTHBOUND SUBTOTALS OF CLASS A PATCH, 10 INCH					20.0	82.7	56.0	40.0	1219.0	110.0	198.7

FILE NAME =	USER NAME = bergenej	DESIGNED - AJB	REVISED	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pwork\pwidot\bergenej\0262495\059928-sht-schedule.CEL		DRAWN - AJB	REVISED -			39	DS PATCHING 2012-2	MCLEAN	13	10
	PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -		SCALE: N/A					
	PLOT DATE = 4/26/2011	DATE - 3/4/2011	REVISED -		SHEET NO. 1 OF 4 SHEETS					
CONTRACT NO. 70928										
[ILLINOIS] FED. AID PROJECT										