



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 7, 2011

SUBJECT: FAP Route 310 (US 67/IL 104)
Project NHF-HPP-0310 (145)
Section 69-3 (3HB)
Morgan County
Contract No. 72667
Item No. 156, June 17, 2011 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised sheets 4, 16 and 18-20 of the Plans.
3. Revised page iv of the Table of Contents to the Special Provisions.
4. Added page 163 & 164 to the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Roger Driskell, Region 4, District 6; Mike Renner; D. Carl Puzey;
Estimates

TBW:DB:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0322118	REM CON FLAR END SEC	EACH	1.000				
X0323716	ACCESS GATE DOUBLE 30	EACH	1.000				
X0325607	GR STAB GEOSYNTHETIC	SQ YD	7,500.000				
X0325712	RELOC EXIST ELEC SYS	L SUM	1.000				
X0326911	TRANSVERSE DRAINS COM	EACH	31.000				
X0327009	REMOVE SIGN SPECIAL	EACH	8.000				
X0327297	REMOVE BARRICADES	EACH	2.000				
X0358300	REM & RELAY END SECT	EACH	2.000				
X2020500	EARTH EXC - ROCKFILL	CU YD	4,300.000				
X2070304	POROUS GRAN EMB SPEC	CU YD	322.300				
X2503000	MAINTENANCE MOWING	ACRE	160.000				
X2810208	STONE RIPRAP CL A4 SP	TON	1,799.000				
X2810210	STONE RIPRAP CL A5 SP	TON	1,391.000				
X5015225	PIPE CULVERT REM SPL	FOOT	81.000				
X5428800	CIP RC END SEC	CU YD	75.200				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X6060424	COMB CC&G TB4.24	FOOT	440.000				
X6063600	COMB CC&G TM4.24	FOOT	51.000				
X6064201	COMB CC&G TM4.06	FOOT	2,243.000				
X6065701	CONC MED TSM4.06	SQ FT	4,654.000				
X7800620	URETH PAVT MK LINE 5	FOOT	270,604.000				
X7800630	URETH PAVT MK LINE 6	FOOT	10,968.000				
X7800640	URETH PAVT MK LINE 8	FOOT	3,978.000				
X7800650	URETH PAVT MK LINE 12	FOOT	2,004.000				
Z0002700	BARRICADES	EACH	4.000				
Z0007121	WELD WIRE FABRIC	SQ FT	365.000				
Z0007601	BLDG REMOV NO 1	L SUM	1.000				
Z0007602	BLDG REMOV NO 2	L SUM	1.000				
Z0007603	BLDG REMOV NO 3	L SUM	1.000				
Z0007604	BLDG REMOV NO 4	L SUM	1.000				
Z0007605	BLDG REMOV NO 5	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0007606	BLDG REMOV NO 6	L SUM	1.000				
Z0007607	BLDG REMOV NO 7	L SUM	1.000				
Z0007608	BLDG REMOV NO 8	L SUM	1.000				
Z0007609	BLDG REMOV NO 9	L SUM	1.000				
Z0010616	ROADWAY CLEANING SPL	EACH	2.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0023602	GRAN CULVERT BACKFILL	CU YD	2,000.000				
Z0023900	FILL EXIST WELLS	EACH	5.000				
Z0030150	IMPACT ATTEN NRD TL3	EACH	2.000				
Z0041500	PLUG EX CULVERTS	EACH	4.000				
Z0046304	P UNDR FOR STRUCT 4	FOOT	220.000				
Z0054515	ROCK FILL - EMBANK	TON	10,700.000				
Z0054517	ROCK FILL - FOUNDATN	TON	600.000				
Z0054530	ROCK FILL - SUBGRADE	TON	6,100.000				
Z0056100	SAND DRAINAGE BLANKET	CU YD	1,200.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0065796	RIPRAP SLURRY	SQ YD	1,671.000				
20100110	TREE REMOV 6-15	UNIT	299.000				
20100210	TREE REMOV OVER 15	UNIT	534.000				
20100500	TREE REMOV ACRES	ACRE	18.900				
* 20200100	EARTH EXCAVATION	CU YD	647,963.000				
20200200	ROCK EXCAVATION	CU YD	100.000				
20200500	EARTH EXC WID	CU YD	130.000				
* 20400800	FURNISHED EXCAVATION	CU YD	436,880.000				
20700220	POROUS GRAN EMBANK	CU YD	40.000				
20800150	TRENCH BACKFILL	CU YD	4,665.000				
21101615	TOPSOIL F & P 4	SQ YD	877,140.000				
21301060	EXPLOR TRENCH 60	FOOT	50,000.000				
21400100	GRADING & SHAP DITCH	FOOT	500.000				
25000200	SEEDING CL 2	ACRE	230.000				
25000350	SEEDING CL 7	ACRE	40.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
25000400	NITROGEN FERT NUTR	POUND	20,700.000				
25000500	PHOSPHORUS FERT NUTR	POUND	20,700.000				
25000600	POTASSIUM FERT NUTR	POUND	20,700.000				
25000700	AGR GROUND LIMESTONE	TON	460.000				
25003200	INTERSEED CL 2	ACRE	10.000				
25100115	MULCH METHOD 2	ACRE	270.000				
25100635	HD EROS CONTR BLANKET	SQ YD	7,197.000				
28000200	EARTH EXC - EROS CONT	CU YD	1,000.000				
28000250	TEMP EROS CONTR SEED	POUND	75,000.000				
28000400	PERIMETER EROS BAR	FOOT	7,000.000				
28000500	INLET & PIPE PROTECT	EACH	80.000				
28001000	AGGREGATE - EROS CONT	TON	1,500.000				
28100707	STONE DUMP RIP CL A4	SQ YD	19,885.000				
28100709	STONE DUMP RIP CL A5	SQ YD	426.000				
28100711	STONE DUMP RIP CL A6	SQ YD	1,187.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
28100825	STONE DUMP RIP CL B3	TON	600.000				
28200200	FILTER FABRIC	SQ YD	24,854.000				
31000600	PR LIM STAB SOIL M 12	SQ YD	398,278.000				
31001500	LIME	TON	7,969.000				
31100100	SUB GRAN MAT A	TON	2,200.000				
31101900	SUB GRAN MAT C	TON	24,402.000				
31200100	STAB SUBBASE 4	SQ YD	261,698.000				
35100100	AGG BASE CSE A	TON	379.000				
35100700	AGG BASE CSE A 8	SQ YD	31,771.000				
35501316	HMA BASE CSE 8	SQ YD	12,642.000				
35501320	HMA BASE CSE 9	SQ YD	20,270.000				
35501332	HMA BASE CSE 12	SQ YD	6,708.000				
35600708	HMA BC WID 8	SQ YD	65.000				
35600712	HMA BC WID 9	SQ YD	460.000				
40200100	AGG SURF CSE A	TON	5,956.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
40200700	AGG SURF CSE A 8	SQ YD	1,870.000				
40200800	AGG SURF CSE B	TON	2,500.000				
40201000	AGGREGATE-TEMP ACCESS	TON	2,000.000				
40600200	BIT MATLS PR CT	TON	94.000				
40600300	AGG PR CT	TON	153.000				
40600625	LEV BIND MM N50	TON	2,251.000				
40600635	LEV BIND MM N70	TON	344.000				
40600825	P LEV BIND MM N50	TON	55.000				
40600837	P LEV BIND MM N70	TON	302.000				
40600895	CONSTRUC TEST STRIP	EACH	4.000				
40600982	HMA SURF REM BUTT JT	SQ YD	605.000				
40600990	TEMPORARY RAMP	SQ YD	500.000				
40603080	HMA BC IL-19.0 N50	TON	5,464.000				
40603085	HMA BC IL-19.0 N70	TON	1,433.000				
40603230	P HMA BC IL19.0 N50	TON	196.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
40603310	HMA SC "C" N50	TON	6,993.000				
40603340	HMA SC "D" N70	TON	619.000				
40603510	P HMA SC "C" N50	TON	279.000				
40603540	P HMA SC "D" N70	TON	844.000				
40800050	INCIDENTAL HMA SURF	TON	840.000				
42000501	PCC PVT 10 JOINTED	SQ YD	234,743.000				
42001200	PAVEMENT FABRIC	SQ YD	10,115.000				
42001300	PROTECTIVE COAT	SQ YD	351,445.000				
42100300	CONT REINF PCC PVT 10	SQ YD	1,260.000				
42300200	PCC DRIVEWAY PAVT 6	SQ YD	108.000				
42300400	PCC DRIVEWAY PAVT 8	SQ YD	381.000				
42400100	PC CONC SIDEWALK 4	SQ FT	538.000				
44000100	PAVEMENT REM	SQ YD	102,502.000				
44000157	HMA SURF REM 2	SQ YD	2,385.000				
44000161	HMA SURF REM 3	SQ YD	651.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44000200	DRIVE PAVEMENT REM	SQ YD	825.000				
44000300	CURB REM	FOOT	1,035.000				
44000600	SIDEWALK REM	SQ FT	737.000				
44004000	PAVED DITCH REMOVAL	FOOT	310.000				
44004250	PAVED SHLD REMOVAL	SQ YD	1,812.000				
44200202	PAVT PATCH T2 17	SQ YD	43.000				
44200204	PAVT PATCH T3 17	SQ YD	21.000				
44200206	PAVT PATCH T4 17	SQ YD	169.000				
48101200	AGGREGATE SHLDS B	TON	26,325.000				
48203029	HMA SHOULDERS 8	SQ YD	7,730.000				
48203100	HMA SHOULDERS	TON	294.000				
48300500	PCC SHOULDERS 10	SQ YD	111,158.000				
50100300	REM EXIST STRUCT N1	EACH	1.000				
50100400	REM EXIST STRUCT N2	EACH	1.000				
50100500	REM EXIST STRUCT N3	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50100600	REM EXIST STRUCT N4	EACH	1.000				
50100700	REM EXIST STRUCT N5	EACH	1.000				
50100800	REM EXIST STRUCT N6	EACH	1.000				
50100900	REM EXIST STRUCT N7	EACH	1.000				
50101000	REM EXIST STRUCT N8	EACH	1.000				
50101100	REM EXIST STRUCT N9	EACH	1.000				
50101200	REM EXIST STRUCT N10	EACH	1.000				
50105220	PIPE CULVERT REMOV	FOOT	4,930.000				
50200100	STRUCTURE EXCAVATION	CU YD	214.100				
50300225	CONC STRUCT	CU YD	240.600				
50300255	CONC SUP-STR	CU YD	721.400				
50300260	BR DECK GROOVING	SQ YD	1,634.000				
50300280	CONCRETE ENCASEMENT	CU YD	14.200				
50300300	PROTECTIVE COAT	SQ YD	2,141.000				
50401105	F & E P P CON I-BM 54	FOOT	2,200.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50800105	REINFORCEMENT BARS	POUND	90,670.000				
50800205	REINF BARS, EPOXY CTD	POUND	189,300.000				
50800515	BAR SPLICERS	EACH	138.000				
51100100	SLOPE WALL 4	SQ YD	713.000				
51201610	FUR STL PILE HP12X63	FOOT	1,968.000				
51201800	FUR STL PILE HP14X73	FOOT	2,448.000				
51202305	DRIVING PILES	FOOT	4,416.000				
51203800	TEST PILE ST HP14X73	EACH	2.000				
51500100	NAME PLATES	EACH	1.000				
54001001	BOX CUL END SEC C1	EACH	1.000				
54002020	EXPAN BOLTS 3/4	EACH	109.000				
54003000	CONC BOX CUL	CU YD	418.300				
54010303	PCBC 3X3	FOOT	4.000				
54010503	PCBC 5X3	FOOT	144.000				
54010806	PCBC 8X6	FOOT	116.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
542A0217	P CUL CL A 1 12	FOOT	52.000				
542A0229	P CUL CL A 1 24	FOOT	256.000				
542A0235	P CUL CL A 1 30	FOOT	124.000				
542A1063	P CUL CL A 2 18	FOOT	72.000				
542A1069	P CUL CL A 2 24	FOOT	2,258.000				
542A1075	P CUL CL A 2 30	FOOT	1,050.000				
542A1081	P CUL CL A 2 36	FOOT	766.000				
542A1087	P CUL CL A 2 42	FOOT	170.000				
542A1093	P CUL CL A 2 48	FOOT	634.000				
542A1099	P CUL CL A 2 54	FOOT	54.000				
542A1105	P CUL CL A 2 60	FOOT	680.000				
542A1111	P CUL CL A 2 66	FOOT	182.000				
542A1117	P CUL CL A 2 72	FOOT	328.000				
542A1909	P CUL CL A 3 24	FOOT	348.000				
542A1915	P CUL CL A 3 30	FOOT	94.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
542A1927	P CUL CL A 3 42	FOOT	156.000				
542A1933	P CUL CL A 3 48	FOOT	74.000				
542A1939	P CUL CL A 3 54	FOOT	60.000				
542A2749	P CUL CL A 4 24	FOOT	252.000				
542A2755	P CUL CL A 4 30	FOOT	68.000				
542A4027	P CUL CL A 6 42	FOOT	230.000				
542A5473	P CUL CL A 1 EQRS 18	FOOT	124.000				
542A5482	P CUL CL A 1 EQRS 27	FOOT	62.000				
542A5485	P CUL CL A 1 EQRS 30	FOOT	56.000				
542A5491	P CUL CL A 1 EQRS 36	FOOT	52.000				
542A5497	P CUL CL A 1 EQRS 42	FOOT	148.000				
542A8227	P CUL CL A 2 EQRS 42	FOOT	164.000				
542D0217	P CUL CL D 1 12	FOOT	80.000				
542D0220	P CUL CL D 1 15	FOOT	1,306.000				
542D0223	P CUL CL D 1 18	FOOT	566.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
542D0229	P CUL CL D 1 24	FOOT	340.000				
542D0235	P CUL CL D 1 30	FOOT	128.000				
542D0241	P CUL CL D 1 36	FOOT	168.000				
542D0247	P CUL CL D 1 42	FOOT	128.000				
542D1063	P CUL CL D 2 18	FOOT	86.000				
542D1069	P CUL CL D 2 24	FOOT	424.000				
542D1075	P CUL CL D 2 30	FOOT	154.000				
542D1081	P CUL CL D 2 36	FOOT	312.000				
542D1129	P CUL CL D 2 84	FOOT	62.000				
542D1915	P CUL CL D 3 30	FOOT	110.000				
542D5470	P CUL CL D 1 EQRS 15	FOOT	60.000				
542D5473	P CUL CL D 1 EQRS 18	FOOT	198.000				
5421D012	P CUL CL D 1 12 TEMP	FOOT	772.000				
5421D015	P CUL CL D 1 15 TEMP	FOOT	122.000				
5421D018	P CUL CL D 1 18 TEMP	FOOT	314.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
5421D024	P CUL CL D 1 24 TEMP	FOOT	84.000				
5421D042	P CUL CL D 1 42 TEMP	FOOT	58.000				
54213657	PRC FLAR END SEC 12	EACH	1.000				
54213663	PRC FLAR END SEC 18	EACH	2.000				
54213669	PRC FLAR END SEC 24	EACH	43.000				
54213675	PRC FLAR END SEC 30	EACH	16.000				
54213681	PRC FLAR END SEC 36	EACH	4.000				
54213687	PRC FLAR END SEC 42	EACH	6.000				
54213693	PRC FLAR END SEC 48	EACH	4.000				
54213705	PRC FLAR END SEC 60	EACH	3.000				
54213711	PRC FLAR END SEC 66	EACH	2.000				
54213717	PRC FLAR END SEC 72	EACH	4.000				
54214503	PRC FL END S EQ RS 18	EACH	4.000				
54214512	PRC FL END S EQ RS 27	EACH	2.000				
54214515	PRC FL END S EQ RS 30	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
54214521	PRC FL END S EQ RS 36	EACH	2.000				
54214527	PRC FL END S EQ RS 42	EACH	2.000				
54215454	CIP RC END SEC 54	EACH	2.000				
54215547	MET END SEC 12	EACH	8.000				
54215550	MET END SEC 15	EACH	43.000				
54215553	MET END SEC 18	EACH	24.000				
54215559	MET END SEC 24	EACH	32.000				
54215565	MET END SEC 30	EACH	10.000				
54215571	MET END SEC 36	EACH	14.000				
54215577	MET END SEC 42	EACH	6.000				
54215619	MET END SEC 84	EACH	2.000				
54215760	MET END SEC EQV RS 15	EACH	2.000				
54215763	MET END SEC EQV RS 18	EACH	10.000				
54218440	R C PIPE TEE 36P 36R	EACH	1.000				
54218484	R C PIPE TEE 60P 36R	EACH	3.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
54218506	R C PIPE TEE 72P 36R	EACH	1.000				
5422A024	P CUL CL A 2 24 TEMP	FOOT	24.000				
5422D024	P CUL CL D 2 24 TEMP	FOOT	212.000				
5422D030	P CUL CL D 2 30 TEMP	FOOT	120.000				
5422D036	P CUL CL D 2 36 TEMP	FOOT	60.000				
54247130	GRATING-C FL END S 24	EACH	1.000				
54248510	CONCRETE COLLAR	CU YD	3.800				
550A0050	STORM SEW CL A 1 12	FOOT	79.000				
59300100	CONTR LOW-STRENG MATL	CU YD	58.000				
60100060	CONC HDWL FOR P DRAIN	EACH	304.000				
60100925	PIPE DRAINS 8	FOOT	2,000.000				
60100935	PIPE DRAINS 10	FOOT	2,000.000				
60100945	PIPE DRAINS 12	FOOT	4,048.000				
60100955	PIPE DRAINS 15	FOOT	1,000.000				
60107600	PIPE UNDERDRAINS 4	FOOT	117,864.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60108100	PIPE UNDERDRAIN 4 SP	FOOT	4,105.000				
60221000	MAN TA 5 DIA T1F OL	EACH	1.000				
60221100	MAN TA 5 DIA T1F CL	EACH	7.000				
60222270	MAN TA 5 DIA T3V F&G	EACH	1.000				
60222805	MAN TA 5D M IN 604106	EACH	21.000				
60224071	MAN TA 6D M IN 604106	EACH	1.000				
60224446	MAN TA 7 DIA T1F CL	EACH	1.000				
60236200	INLETS TA T8G	EACH	6.000				
60237000	INLETS TA T15F&L	EACH	2.000				
60240301	INLETS TB T8G	EACH	1.000				
60246805	MED INLET (604106)	EACH	5.000				
60500040	REMOV MANHOLES	EACH	1.000				
60500060	REMOV INLETS	EACH	3.000				
60608600	COMB CC&G TM6.06	FOOT	18.000				
60610400	COMB CC&G TM6.24	FOOT	44.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60618300	CONC MEDIAN SURF 4	SQ FT	17,351.000				
60624600	CORRUGATED MED	SQ FT	706.000				
61000225	TY F INLET BOX 610001	EACH	4.000				
61100605	MISC CONCRETE	CU YD	100.000				
61101009	STORM SEW PROT A 8	FOOT	500.000				
61101011	STORM SEW PROT A 10	FOOT	500.000				
61101013	STORM SEW PROT A 12	FOOT	8,000.000				
61101020	STORM SEW PROT A 18	FOOT	500.000				
63000001	SPBGR TY A 6FT POSTS	FOOT	562.520				
63100085	TRAF BAR TERM T6	EACH	4.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	4.000				
63200310	GUARDRAIL REMOV	FOOT	880.000				
63500105	DELINEATORS	EACH	593.000				
64200105	SHOULDER RUMBLE STRIP	FOOT	111,654.000				
66400105	CH LK FENCE 4	FOOT	4,623.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
66500105	WOV W FENCE 4	FOOT	31,684.000				
66501600	WOV W GATES 4X16 DBL	EACH	2.000				
66600105	FUR ERECT ROW MARKERS	EACH	271.000				
66700205	PERM SURV MKRS T1	EACH	33.000				
66700305	PERM SURV MKRS T2	EACH	22.000				
*ADD 66900105	UNDERGR STOR TANK REM	EACH	1.000				
*ADD 66900200	NON SPL WASTE DISPOSL	CU YD	15,700.000				
*ADD 66900400	SPL WAST GRD WAT DISP	GALLON	100,000.000				
*ADD 66900450	SPL WASTE PLNS/REPORT	L SUM	1.000				
*ADD 66900530	SOIL DISPOSAL ANALY	EACH	4.000				
67000400	ENGR FIELD OFFICE A	CAL MO	30.000				
67000600	ENGR FIELD LAB	CAL MO	30.000				
67100100	MOBILIZATION	L SUM	1.000				
70100205	TRAF CONT-PROT 701401	EACH	4.000				
70100450	TRAF CONT-PROT 701201	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70100460	TRAF CONT-PROT 701306	L SUM	1.000				
70100500	TRAF CONT-PROT 701326	L SUM	1.000				
70101830	TRAF CONT-PROT BLR 21	L SUM	1.000				
70101835	TRAF CONT-PROT BLR 22	L SUM	1.000				
70102620	TR CONT & PROT 701501	L SUM	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	36.000				
70300100	SHORT TERM PAVT MKING	FOOT	16,000.000				
70300210	TEMP PVT MK LTR & SYM	SQ FT	3,244.000				
70300230	TEMP PVT MK LINE 5	FOOT	541,208.000				
70300240	TEMP PVT MK LINE 6	FOOT	21,936.000				
70300250	TEMP PVT MK LINE 8	FOOT	7,956.000				
70300260	TEMP PVT MK LINE 12	FOOT	4,008.000				
70300280	TEMP PVT MK LINE 24	FOOT	904.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	130,958.000				
72000100	SIGN PANEL T1	SQ FT	3,465.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
72000200	SIGN PANEL T2	SQ FT	304.000				
72000300	SIGN PANEL T3	SQ FT	1,398.000				
72700100	STR STL SIN SUP BA	POUND	11,506.000				
72800100	TELES STL SIN SUPPORT	FOOT	8,084.000				
73000100	WOOD SIN SUPPORT	FOOT	520.000				
73100100	BASE TEL STL SIN SUPP	EACH	8.000				
73400100	CONC FOUNDATION	CU YD	25.900				
78001110	PAINT PVT MK LINE 4	FOOT	536.000				
78001120	PAINT PVT MK LINE 5	FOOT	88,697.000				
78001180	PAINT PVT MK LINE 24	FOOT	47.000				
78003100	PREF PL PM TB LTR-SYM	SQ FT	1,829.000				
78003180	PREF PL PM TB LINE 24	FOOT	452.000				
78100100	RAISED REFL PAVT MKR	EACH	1,481.000				
78200300	PRISMATIC CURB REFL	EACH	250.000				
78200410	GUARDRAIL MKR TYPE A	EACH	16.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78201000	TERMINAL MARKER - DA	EACH	4.000				
78300100	PAVT MARKING REMOVAL	SQ FT	23,374.000				
78300200	RAISED REF PVT MK REM	EACH	100.000				
80400100	ELECT SERV INSTALL	EACH	5.000				
81028550	UNDRGRD C IM 2	FOOT	1,111.000				
81603000	UD 2#8 #8G XLPUSE 3/4	FOOT	4,210.000				
81603025	UD 2#4 #4G XLPUSE 1	FOOT	2,572.000				
81603035	UD 2#6 #6G XLPUSE 1	FOOT	5,200.000				
81800200	A CBL 2-1C4 MESS WIRE	FOOT	2,150.000				
82103900	LUM SV MM 250W	EACH	46.000				
82500300	LT CONT PM 240V 30	EACH	3.000				
82500310	LT CONT PM 240V 60	EACH	1.000				
83062730	LT P WS 45MH TEN MT	EACH	28.000				
83062735	LT P WS 45MH TN MT-TW	EACH	9.000				
83600355	LP F M 15BC 8" X 6'	EACH	28.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 72667

State Job # - C-96-037-08
 PPS NBR - 6-00241-0100
 County Name - MORGAN- -
 Code - 137 - -
 District - 6 - -
 Section Number - 69-3 (3HB)

Project Number
 NHF-HPP-0310/145/

Route
 FAP 310

* REVISE : JUNE 06, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
83600357	LP F M 15BC 8" X 8'	EACH	9.000				
83800650	BKWY DEV COU SS SCR N	EACH	140.000				

POST MOUNTING OF SIGNS (BDE)..... 119
PRECAST CONCRETE HANDLING HOLES (BDE) 119
RAISED REFLECTIVE PAVEMENT MARKERS (BDE)..... 120
RECLAIMED ASPHALT PAVEMENT (RAP) (BDE) 120
SEEDING (BDE) 127
SELF-CONSOLIDATING CONCRETE FOR CAST-IN-PLACE CONSTRUCTION (BDE)..... 129
SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE)..... 133
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 134
SURFACE TESTING OF PAVEMENTS (BDE) 135
TEMPORARY EROSION CONTROL (BDE) 140
TRAFFIC BARRIER TERMINAL, TYPE 6 (BDE) 144
TRAFFIC CONTROL SURVEILLANCE (BDE) 144
UTILITY COORDINATION AND CONFLICTS (BDE)..... 144
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID) 149
FUEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) 152
STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) 156
APPENDIX D 160
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES 163

Revised 06/07/2011

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES

This work shall be according to Article 669 of the Standard Specifications and the following:

Qualifications. The term environmental firm shall mean an environmental firm with at least five (5) documented leaking underground storage tank (LUST) cleanups or that is pre-qualified in hazardous waste by the Department. Documentation includes but not limited to verifying remediation and special waste operations for sites contaminated with gasoline, diesel, or waste oil in accordance with all Federal, State, or local regulatory requirements and shall be provided to the Engineer for approval. The environmental firm selected shall not be a former or current consultant or have any ties with any of the properties contained within and/or adjacent to this construction project.

General. This Special Provision will likely require the Contractor to subcontract for the execution of certain activities. .

All contaminated materials shall be managed as non-special waste. This work shall include monitoring and potential sampling, analytical testing, and management of a material contaminated by regulated substances. During the Phase I Preliminary Engineering an Underground Storage Tank (UST) was discovered at between 866+20 to 867+80 offset 0 to 20 feet RT/LT.

- A) The Environmental Firm shall continuously monitor for worker protection and the Contractor shall manage and dispose of all soils excavated within the following areas as classified below. The lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit whichever is less. Soil samples or analysis without the approval of the Engineer will be at no additional cost to the Department. Phase I Preliminary Engineering information is available through the District's Environmental Studies Unit.
1. Station 0+80 to Station 2+50 0 to 50 feet LT/RT (Residence, Site 568V-10, 1713 US 67/IL 104) – non-special waste. Contaminants of concern sampling parameters: BETX.
 2. Station 22+50 to Station 24+00 0 to 50 feet RT (Bethel Road District #4, Site 568V-28, 950 Cylinder Head Road) – non-special waste. Contaminants of concern sampling parameters: Arsenic.
 3. All groundwater between Station 872+00 and Station 876+00 0 to 200 feet LT/RT (Residence, Site 568V-10, 1713 US 67/IL 104) – non-special waste. Contaminants of concern sampling parameters: BETX.
 4. All groundwater between Station 900+00 and Station 903+00 0 to 200 feet LT/RT (Vacant Lot, Site 568V-18, 1720 US 67/IL 104) – non-special waste. Contaminants of concern sampling parameters: MTBE.
- B) The Environmental Firm shall continuously monitor for worker protection and the Contractor shall manage any excavated soils **within the construction limits of this project as fill**. Although the soil concentrations exceed a residential property's Tier 1 soil remediation objective for the ingestion exposure pathway, they can be utilized within the construction limits as fill because the roadway is not considered a residential property. All storm sewer excavated soils can be placed back into the excavated trench as backfill unless trench backfill is specified.

Added 06/07/2011

C) If the soils cannot be utilized within the construction limits as fill then they must be managed off-site as a non-special waste. The following areas can be managed within the construction limits as fill.

1. Station 9+00 to Station 12+00 0 to 50 LT/RT (Farmstead and Farmland, Site 568V-5, 1701 Block of US 67/IL 104) – non-special waste. Contaminants of concern sampling parameters: Arsenic.
2. Station 445+50 to Station 447+00 0 to 50 feet RT (Bearcat Junction Gas Station, Site 568V-13, 1715 US 67/IL 104) – non-special waste. Contaminants of concern sampling parameters: Arsenic.
3. Station 901+50 to Station 903+00 0 to 50 feet LT/RT (Vacant Lot, Site 568V-18, 1720 US 67/IL 104) – non-special waste. Contaminants of concern sampling parameters: Arsenic.
4. Station 74+00 to Station 46+00 0 to 50 feet RT (Morgan County Farm Service, Site 568V-22, 1720 Bethel Lane) – non-special waste. Contaminants of concern sampling parameters: Arsenic.
5. Station 25+00 to Station 28+00 0 to 50 feet RT (The CB Shop, Site 568V-23, 1729 US 67/IL 104) – non-special waste. Contaminants of concern sampling parameters: Arsenic.

Added 06/07/2011