

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	69-3(3HB)	MORGAN	793	16
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

3:51:41 PM

Mar-25-2011 03:51:41PM

80% FEDERAL 20% STATE
CONSTRUCTION AND SAFETY TYPE CODE

CODE NO.	ITEM	SP. PROV.	UNIT	TOTAL QUANTITIES	CONSTRUCTION AND SAFETY TYPE CODE						
					0001 ROADWAY	0008 STRUCTURE					
X0327009	REMOVE SIGN (SPECIAL)	.	EACH	8	8						
X0358300	REMOVE AND RELAY END SECTIONS	.	EACH	2	2						
X2020500	EARTH EXCAVATION (ROCKFILL)	.	CU YD	4300	4300						
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	.	CU YD	322.3		322.3					
X2503000	MAINTENANCE MOWING	.	ACRE	160	160						
X2810208	STONE RIPRAP, CLASS A4 (SPECIAL)	.	TON	1799	1799						
X2810210	STONE RIPRAP, CLASS A5 (SPECIAL)	.	TON	1391	1391						
X5015225	PIPE CULVERT REMOVAL (SPECIAL)	.	FOOT	81	81						
X5428800	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS	.	CU YD	75.2	75.2						
X6060424	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-4.24	.	FOOT	440	440						
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	.	FOOT	51	51						
X6064201	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.06	.	FOOT	2243	2243						
X6065701	CONCRETE MEDIAN, TYPE SM-4.06	.	SQ FT	4654	4654						
X7240205	REMOVE SIGN COMPLETE	.	EACH	30	30						
* X7800620	URETHANE PAVEMENT MARKING - LINE 5"	.	FOOT	270604	270604						
* X7800630	URETHANE PAVEMENT MARKING - LINE 6"	.	FOOT	10968	10968						
* X7800640	URETHANE PAVEMENT MARKING - LINE 8"	.	FOOT	3978	3978						
* X7800650	URETHANE PAVEMENT MARKING - LINE 12"	.	FOOT	2004	2004						
* 66900105	UNDERGROUND STORAGE TANK REMOVAL	.	EACH	1	1						
* 66900200	NON-SPECIAL WASTE DISPOSAL	.	CU YD	15,700	15,700						
* 66900400	SPECIAL WASTE GROUNDWATER DISPOSAL	.	GAL	100,000	100,000						
* 66900450	SPECIAL WASTE PLANS AND REPORTS	.	L SUM	1	1						
* 66900530	SOIL DISPOSAL ANALYSIS	.	EACH	4	4						

*SPECIALTY ITEM

⚠ REVISION 6-6-11

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
FAP 310 (US 67/IL 104)
SHEET 13 OF 13

DATE 10/2010
DRAWN BY 86J
CHECKED BY EBB

\$FILES