

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	69-3(3HB)	MORGAN	793	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

80% FEDERAL 20% STATE
CONSTRUCTION AND SAFETY TYPE CODE

CODE NO.	ITEM	SP. PROV.	UNIT	TOTAL QUANTITIES	CONSTRUCTION AND SAFETY TYPE CODE	
					0001 ROADWAY	0008 STRUCTURE
* 73400100	CONCRETE FOUNDATIONS		CU YD	25.9	25.9	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"		FOOT	536	536	
* 78001120	PAINT PAVEMENT MARKING - LINE 5"		FOOT	88697	88697	
* 78001180	PAINT PAVEMENT MARKING - LINE 24"		FOOT	47	47	
* 78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS		SO FT	1829	1829	
* 78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"		FOOT	452	452	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER		EACH	1481	1481	
* 78200300	PRISMATIC CURB REFLECTOR		EACH	250	250	
* 78200410	GUARDRAIL MARKERS, TYPE A		EACH	16	16	
* 78201000	TERMINAL MARKER - DIRECT APPLIED		EACH	4	4	
* 78300100	PAVEMENT MARKING REMOVAL		SO FT	23374	23374	
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL		EACH	100	100	
* 80400100	ELECTRIC SERVICE INSTALLATION		EACH	5	5	
* 81028550	UNDERGROUND CONDUIT, INTERMEDIATE METAL, 2" DIA.		FOOT	1,111	1,111	
* 81603000	UNIT DUCT, 600V, 2-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE		FOOT	4,210	4,210	
* 81603025	UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.4 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE		FOOT	2,572	2,572	
* 81603035	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE		FOOT	5200	5200	
* 81800200	AERIAL CABLE, 2-1/C NO. 4 WITH MESSENGER WIRE		FOOT	2150	2150	
* 82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT		EACH	46	46	
* 82500300	LIGHTING CONTROLLER, POLE MOUNTED, 240 VOLT, 30 AMP		EACH	3	3	
* 82500310	LIGHTING CONTROLLER, POLE MOUNTED, 240 VOLT, 60 AMP		EACH	1	1	
* 83062730	LIGHT POLE, WEATHERING STEEL, 45 FT. M.H., TENON MOUNT		EACH	28	28	
* 83062735	LIGHT POLE, WEATHERING STEEL, 45 FT. M.H., TENON MOUNT - TWIN		EACH	9	9	
* 83600355	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 6"		EACH	28	28	
* 83600357	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 8"		EACH	9	9	
* 83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN		EACH	140	140	
* 84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION		EACH	1	1	
* X0325712	RELOCATE EXISTING ELECTRICAL SYSTEM		L SUM	1	1	
* X0327297	REMOVE BARRICADES		EACH	2	2	

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAP 310 (US 67/IL 104)
SHEET 11 OF 13
DATE 10/2010
DRAWN BY BGJ
CHECKED BY EBB

2:26:24 PM
Mar-30-2011 02:26:24 PM
\$FILE\$