

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	69-3(3HB)	MORGAN	793	39
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CAST-IN-PLACE CONCRETE SCHEDULE

STRUCTURE NO.	STATION	SIDE	C.I.P. REINF	C.I.P. REINF	REINF BARS	WELDED WIRE FABRIC	CONCRETE BOX CULVERTS	CONCRETE COLLARS	EXPANSION BOLTS 3/4 INCH	GRANULAR CULVERT BACKFILL
			END SECT	END SECT 54"	POUND	SQ FT	CU YD	EACH	CU YD	
FAP 310 (US 67)										
9	851+11.0	LT & RT	5.0		230					
14	866+07.0	LT			15		0.4	9		
24	922+38.8	LT & RT	15.0		780					
37	995+49.0	LT & RT	19.1		1250					
41	1019+28.0	LT & RT	5.1		380					
51	1082+59.8	LT	6		65	365	1.2			
54	1092+06.0	LT & RT			7007.0		291.7	40	896	
56	1102+68.7	LT			50		0.7			
57	1102+68.7	RT			50		0.7			
TRANSITION A										
70	971+13.4	LT & RT			35		0.4	4		
71	974+66.0	RT			35		0.4	4		
COOPER STREET										
106	444+96.0	LT & RT			1930		16.4			110
RELOCATED CREWS LANE										
109	45+50.0	LT & RT	3.8		190					
NEW STREET										
110	302+09.0	LT & RT	17.4		1110					
RELOCATED CYLINDER HEAD ROAD										
128	96+65.0	LT & RT	3.8		190					
DUTCH LANE WEST										
157	206+05.0	LT & RT		2						
HART'S GRAVEL ROAD										
158	291+09.2	LT & RT			11900		80.7	52	265	
159	292+61.0	LT & RT			2390		29.5		421	
TOTALS			75.2	2	90670	365	418.3	3.8	109	1692
USE			75.2	2	90670	365	418.3	3.8	109	2000

BOX CULVERT SCHEDULE

STRUCTURE NO.	STATION	SIDE	PRECAST CONCRETE BOX CULVERT	BOX CULVERT	BOX CULVERT
			3'x3'	5'x3'	8'x6'
FAP 310 (US 67)					
14	866+07.0	LT	4		1
COOPER STREET					
106	444+96.0	LT & RT		144	
HART'S GRAVEL ROAD					
159	292+61.0	LT & RT			116
TOTALS			4	144	116

REINFORCED CONCRETE PIPE TEE SCHEDULE

STRUCTURE NO.	STATION	SIDE	REINFORCED CONCRETE PIPE TEE	CONCRETE PIPE TEE
			36" PIPE 36" RISER	60" PIPE 36" RISER
FAP 310 (US 67)				
9	851+11.0	LT & RT	1	
13	866+07.0	LT & RT		1
17	877+21.0	LT & RT		1
24	922+38.8	LT & RT		1
41	1019+28.0	LT & RT		1
TOTALS			1	3

STORM SEWER SCHEDULE

STRUCTURE NO.	STATION	SIDE	S.S. CL A	TRENCH BACKFILL
			TY 1 12"	CU YD
COOPER STREET				
103	444+05.0	RT	75	13.4
105	444+82.0	RT	4	0.7
TOTALS			79	14.1

REMOVE AND RELAY END SECTION

STRUCTURE NO.	STATION	SIDE	EACH
FAP 310 (US 67)			
1	779+70.0	LT	1
3	797+00.0	RT	1
TOTAL			2

REMOVE CONCRETE FLARED END SECTIONS

STATION	SIDE	EACH
FAP 310 (US 67)		
770+90.0	RT	1
TOTAL		1

GRATING FOR CONCRETE FLARED END SECTION 24"

STRUCTURE NO.	STATION	SIDE	EACH
FAP 310 (US 67)			
25	931+90.0	RT	1
TOTAL			1

FILLING EXISTING CULVERT SCHEDULE

STATION	SIDE	SIZE	CONTROLLED LOW STRENGTH MATERIAL	PLUG EXISTING CULVERTS
			CU YD	EACH
FAP 310 (US 67)				
770+90.0	RT	24"	7.3	1
971+16.4	LT	2' BY 2'	9.0	1
1093+40.0	LT & RT	36"	41.1	1
COOPER STREET				
444+15.0	RT	12"		1
TOTAL			57.4	4
USE			58	4

SHOULDER DRAIN SCHEDULE

STRUCTURE NO.	STATION	SIDE	TYPE F INLET BOX	PIPE DRAINS 12"	METAL END SECTIONS 12"
			EACH	FOOT	EACH
CONCORD ROAD					
78A	17+64.0	LT	1	12	1
78B	17+64.0	RT	1	12	1
83A	22+36.0	LT	1	12	1
83B	22+36.0	RT	1	12	1
TOTALS			4	48	4

REMOVING MANHOLES

STATION	SIDE	EACH
FAP 310 (US 67)		
770+90.0	RT	1
TOTAL		1

REMOVING INLETS

STATION	SIDE	EACH
FAP 310 (US 67)		
901+64.2	LT	1
1102+56.1	LT	1
COOPER STREET		
445+06.2	RT	1
TOTAL		3

ROADWAY CLEANING (SPECIAL)

STATION TO STATION	SIDE	WIDTH	EACH	
FAP 310 (US 67)				
762+05.0	770+65.0	RT	0-37	1
777+86.6	779+95.4	LT	0-24	1
TOTAL				2

FILLING EXISTING WELLS

STATION	SIDE	OFFSET	EACH
FAP 310 (US 67)			
869+07.90	LT	14.5	1
873+39.70	LT	116.0	1
930+05.70	RT	42.5	1
1111+65.90	LT	99.4	1
1112+27.30	RT	87.5	1
TOTAL			5

IMPACT ATTENUATORS (NON-REDIRECTIVE) TEST LEVEL 3

STATION	SIDE	EACH
FAP 310 (US 67)		
807+38	RT	1
808+25	LT	1
TOTAL		2

REMOVE SIGN (SPECIAL)

STATION	SIDE	OFFSET	DESCRIPTION	EACH
FAP 310 (US 67)				
805+23.7	LT	34.3	TRIOPIA CUSD SIGN	1
886+22.0	LT	113.7	OLD BUSINESS SIGN	1
954+78.1	LT	154.9	CYLINDER HEAD SIGN	1
956+88.0	LT	253.5	CYLINDER HEAD SIGN	1
960+40.8	LT	40.3	CYLINDER HEAD SIGN	1
995+70.0	RT	135.6	ST. PAUL LUTHERAN CHURCH	1
OLD CYLINDER HEAD ROAD				
1+74.7	RT	10.3		1
ASH STREET				
9+43.1	RT	27.9	CHAPIN CHRISTIAN CHURCH & LIONS INTERNATIONAL	1
TOTAL				8

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF QUANTITIES  
 FAP 310 (US 67/IL 104)  
 SHEET 23 OF 42

DATE 10/10  
 DRAWN BY EBB  
 CHECKED BY