

3:57:20 PM

Mar-25-2011 03:57:20PM

\$FILE\$

CONTRACT NO. 72667

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	69-3(3HB)	MORGAN	793	45
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

LIGHTING SCHEDULE

PAY ITEM DESCRIPTION	CONCORD RD INTERCHANGE	RELOCATED CREW LANE	BETHEL LANE INTERSECTION	ST. PAUL'S CHURCH RD INTERSECTION	WEST CROSSOVER	TOTALS
ELECTRIC SERVICE INSTALLATION	1	1	1	1	1	5
UNDERGROUND CONDUIT, 2" DIA., INTERMEDIATE METAL	561	230	170	150		1111
UNIT DUCT, 600V, 2-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE		1500	1300	1310		4210
UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.4 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	2592					2592
UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE						5200
AERIAL CABLE, 2-1/C NO. 4 WITH MESSENGER WIRE					2150	2150
LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	21	9	8	8		46
LIGHTING CONTROLLER PHOTOCELL RELAY		1	1	1		3
LIGHT POLE, WEATHERING STEEL, 45 FT. M.H., TENON MOUNT	15	5	4	4		28
LIGHT POLE, WEATHERING STEEL, 45 FT. M.H., TENON MOUNT - TWIN	3	2	2	2		9
LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 6"	15	5	4	4		28
LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 8"	3	2	2	2		9
BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	64	28	24	24		140
RELOCATE EXISTING ELEC. SYSTEM (FROM EXISTING CROSS-OVER)					1	1

LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 60AMP

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF QUANTITIES  
 FAP 310 (US 67/IL 104)  
 SHEET 29 OF 42  
 DATE 10/10  
 DRAWN BY EBB  
 CHECKED BY