



ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.S. 579	69-3(3HB)	MORGAN	793	336
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SHEET NO. 13
OF 20 SHEETS

Contract No. 72667



ELEVATION OF BEAM AT PIER




PLAN OF BEAM AT PIER

INTERIOR BEAM MOMENT TABLE		
	0.4 Sp. 1	Pier
I	(in ⁴) 213715	
I'	(in ⁴) 499417	
S_b	(in ³) 8559	
S_b'	(in ³) 12711	
S_t	(in ³) 7362	
S_t'	(in ³) 33950	
Q	(k/ft.) 1.270	
M_P	(k) 1556	
s_P	(k/ft.) 0.414	0.414
$M_s P$	(k) 289	515
M_t	(k) 693	649
M_{imp}	(k) 154	145


INTERIOR BEAM REACTION TABLE		
	Abut.	Pier 1 Span 1 Pier 2 Span 3
R_P	(k) 62.8	62.8
$R_s P$	(k) 15.5	25.8
R_t	(k) 36.1	30.0
$Imp.$	(k) 8.1	6.8
R_{Total}	(k) 122.5	125.4

* The total $R_s P$, R_t , and impact reactions are assumed to be distributed evenly to each bearing line at a pier regardless of the span ratios. The bearing design at a pier is based on the maximum reactions of either span.


- I : Non-composite moment of inertia of beam section (in⁴).
- I' : Composite moment of inertia of beam section (in⁴).
- S_b : Non-composite section modulus for the bottom fiber of the prestressed beam (in³).
- S_b' : Composite section modulus for the bottom fiber of the prestressed beam (in³).
- S_t : Non-composite section modulus for the top fiber of the prestressed beam (in³).
- S_t' : Composite section modulus for the top fiber of the prestressed beam (in³).
- Q : Un-factored non-composite dead load (kips/ft.).
- M_P : Un-factored moment due to non-composite dead load conservatively taken at 0.5 of the span (kip-ft.).
- s_P : Un-factored long-term composite (superimposed) dead load (kips/ft.).
- $M_s P$: Un-factored moment due to long-term composite (superimposed) dead load (kip-ft.).
- M_t : Un-factored live load moment on the composite section (kip-ft.).
- M_{imp} : Un-factored moment due to impact on the composite section (kip-ft.).




LIFTING LOOP DETAIL




TOP PLATE




BOTTOM PLATE




BAR G4




BAR G5



BAR G6



BAR G1



BAR G2


BILL OF MATERIAL

Item	Unit	Total
Furnishing and Erecting Precast Prestressed Concrete I-Beams, 54"	Ft.	2200


54" PPC I-BEAM DETAILS
C.H. 7 (CONCORD RD.) (F.A.S. 579)
OVER U.S. 67/IL 104 (F.A.P. 310)
MORGAN COUNTY
STA. 807+81.68 - SECTION 69-3(3HB)
S.N. 069-0513

* Fabricator shall locate to miss strands within permissible tolerances.

3/4" ϕ A307 Bolts with lock nuts, typ. Bolts through the concrete web shall be tightened to snug tight only.



PERMANENT BRACING DETAILS FOR 54" PPC I-BEAMS



DETAIL A

Notes:
All material for bracing shall be hot dip galvanized according to AASHTO M111 unless otherwise noted.
Two hardened washers are required for each set of oversized holes.
All holes shall be 15/16" ϕ unless otherwise noted.
5/16" x 3" x 3" plate washers are required over all slotted holes.
All bolts shall be galvanized according to AASHTO M232.
Bracing shall be installed as beams are erected and tightened as soon as possible during erection.
Permanent bracing shall not be paid for separately, but shall be included in the cost of Furnishing and Erecting Precast Prestressed Concrete I-Beams.