

PAVEMENT SCHEDULE						
LOCATION STATION TO STATION	LENGTH (FT)	WIDTH (FT)	HOT-MIX ASPHALT SURF. REM. 6 1/4" (SQ YD)	BIT. MAT. PRIME CT. (TON)	POLYMERIZED HMA BINDER COURSE, IL-19.0, N105 (THICK. 4 3/4") (TON)	POLYMERIZED HMA SURFACE COURSE, MIX "E", N105 (THICK. 1 1/2") (TON)
<b>I-55</b>						
STA. 307+00.00 TO STA. 324+00.00	1,700.00	12	2267	1	603	191
<b>TOTAL</b>			<b>2,267</b>	<b>1</b>	<b>603</b>	<b>191</b>

URETHANE PAVEMENT MARKING-LINE 5" SCHEDULE	
LOCATION STATION TO STATION	OUTSIDE EDGE LINE 5" WHITE (FT)
<b>I-55</b>	
STA. 307+00.00 TO STA. 313+00.00	600.00
STA. 323+12.00 TO STA. 324+00.00	88.00
<b>TOTAL</b>	
<b>688</b>	

RAISED REFLECTIVE PAVEMENT MARKERS SCHEDULE						
LOCATION STATION TO STATION	LENGTH (FT)	LANE LOCATION	NO. OF LANES	NO. OF REFL. PER SPACING	CRYSTAL (EACH)	REMOVAL (EACH)
<b>I-55</b>						
STA. 307+00.00 TO STA. 324+00.00	1700	CENTER-LINE	1	2 PER 80	44	44
<b>TOTAL</b>					<b>44</b>	<b>44</b>

PORTABLE CHANGEABLE MESSAGE SIGN				
LOCATION STATION TO STATION	TYPE OF WORK	NUMBER NEEDED	APPROX. DURATION (CAL MO)	TOTAL (CAL MO)
I-55 SOUTH BOUND	ADVANCED WARNING	2	0.5	1
I-72	ADVANCED WARNING	1	0.5	0.5
CLEAR LAKE AVE	ADVANCED WARNING	2	0.5	1
DIRKSEN PARKWAY	ADVANCED WARNING	1	0.5	0.5
<b>TOTAL</b>				<b>3</b>

SHORT-TERM PAVEMENT MARKING						
LOCATION STATION TO STATION	DESCRIPTION	LENGTH (FT)	SPACING	NUMBER OF APPLICATIONS	SHORT-TERM PAVE MARK (FT)	WORK ZONE PAVE MARK REM (SQ FT)
<b>I-55</b>						
STA. 307+00.00 TO STA. 313+00.00	SEE NOTE 1	600.00	4' @ 100'	1	24.00	8.00
	SEE NOTE 1					
STA. 320+23.00 TO STA. 324+00.00	SEE NOTE 1	377.00	4' @ 100'	1	15.00	5.00
<b>TOTAL</b>					<b>39</b>	<b>13</b>

NOTE 1. EDGE LINE MARKING 45° DIAGONAL

URETHANE PAVEMENT MARKING-LINE 5" SCHEDULE	
LOCATION STATION TO STATION	OUTSIDE EDGE LINE 5" WHITE (FT)
<b>I-55</b>	
STA. 307+00.00 TO STA. 313+00.00	600.00
STA. 323+12.00 TO STA. 324+00.00	88.00
<b>TOTAL</b>	
<b>688</b>	

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B SCHEDULE			
LOCATION STATION TO STATION	LENGTH	CENTERLINE 5" SKIP-DASH WHITE (FT)	OUTSIDE EDGE LINE 8" SOLID WHITE (FT)
<b>I-55</b>			
STA. 307+00.00 TO STA. 324+00.00	1700.00	425.00	
STA. 320+23.00 TO STA. 323+12.00	289.00		289.00
<b>TOTAL</b>		<b>425</b>	<b>289</b>

FILE NAME =	USER NAME = laughl1nr1	DESIGNED -	REVISED -
et:\pw\work\p\midot\laughl1nr1\d0255556\0672E08-sh-t-schedule.dgn		DRAWN -	REVISED -
	PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = Feb-07-2011 03:10:49PM	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	(84-3-2) I-3	SANGAMON	12	5
CONTRACT NO. 72E08				
ILLINOIS FED. AID PROJECT				