

GENERAL NOTES

Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.

Concrete sealer shall be applied to the designated areas as shown on the plans.

The structural steel shall be cleaned and painted as specified in the special provisions. The concrete substructure units shall be cleaned and sealed as specified in the plans and Standard Specifications.

Only structural steel is to be painted. All other surfaces will be protected from being painted. All paint and overspray will be removed at the Contractor's expense.

The SSPC QP1 Painting Contractor Certification will be required for this project.

Color of the finish coat shall be Gray, Munsell 5B 7/1.

Cleaning and painting of the existing structural steel shall be as specified in the special provision for "Cleaning and Painting Existing Steel Structures". All structural steel, including girders and bearings, shall be cleaned by SSPC-SP10- Near White Metal Blast Cleaning. It is the intent of the Department that the end 2 feet of the girders, lateral bracing within 2 feet of the beam ends, as well as the bearing and masonry plates be cleaned and painted. The existing paint to be removed does not contain lead.

The designated areas cleaned per Near White Metal Blast Cleaning - SSPC-SP10 shall be painted according to the requirements of Paint System 1 - OZ/E/U.

No air monitors will be required.

TOTAL BILL OF MATERIALS

ITEM	UNIT	QUANTITY
Cleaning Bridge Seats	Sq. Ft.	670
Concrete Sealer	Sq. Ft.	670
Cleaning and Painting Steel Bridge No. 1	L Sum	1
Containment and Disposal of Non-Lead Paint Cleaning Residues	L Sum	1

FILE NAME = c:\pwwork\pwwork\swartzr\40262706\077	USER NAME = swartzr 820-structures-0510053.dgn	DESIGNED - KLB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	BRIDGE GENERAL NOTES & BILL OF MATERIALS SN. 051-0053	F.A.S. RTE. 1807	SECTION •	COUNTY Lawrence	TOTAL SHEETS 9	SHEET NO. 4		
PLOT SCALE = 40.0000' / IN.	CHECKED - MEA	REVISED -	SCALE: NA			SHEET NO. 2 OF 3 SHEETS	STA.	TO STA.	CONTRACT NO. 74520			
PLOT DATE = 4/5/2011	DATE - 03/25/11	REVISED -	ILLINOIS FED. AID PROJECT									
• 07 BRIDGE PAINTING 2011-3												