SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ACIM 0004 L01 90% FED. 10% STATE	ACBRI 0011 L1C 90% FED. 10% STATE	ACBRI 0040 L1C 90% FED. 10% STATE	
X5210490	HIGH LOAD MULTI-ROTATIONAL BEARINGS, FIXED - 2000K	EACH	20		20		
X5210180	HIGH LOAD MULTI-ROTATIONAL BEARINGS, GUIDED EXPANSION, 550K	EACH	20		20		
X5210255	HIGH LOAD MULTI-ROTATIONAL BEARINGS, GUIDED EXPANSION, 1700K	EACH	20		20		
87001300	ELECTRIC CABLE IN TRENCH, 600V (XLP-TYPE USE) 3-1/C NO. 6	FOOT	16,255	16,255			
83009210	LIGHT POLE, ALUMINUM, 45 FT. M.H., 2-6 FT. MAST ARMS	EACH	10	10			
X0327277	RELOCATE KIOSK	EACH	1	1			
Z0023902	REMOVE PRESSURE RELIEF WELL	EACH	1	1			
X0327276	STAGED VEHICLE DETECTION AND SURVEILLANCE	L SUM	1	1			
20100500	TREE REMOVAL, ACRES	ACRE	17.75	17.75			
20200100	EARTH EXCAVATION	CU YD	248,055	248,055			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	10237	10237			
20400800	FURNISHED EXCAVATION	CU YD	308,654	308,654			
20700220	POROUS GRANULAR EMBANKMENT	CU YD	10237	10237			
20800150	TRENCH BACKFILL	CU YD	2655	2655			
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	15356	15356			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	172,164	172,164			
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	16396	16396			
~~21301052~~	~~EXPLORATION TRENCH 52" DEPTH~~	~~FOOT~~	~~20000~~	~~20000~~			
* 25000210	SEEDING, CLASS 2A	ACRE	30.75	30.75			
* 25000305	SEEDING, CLASS 3A	ACRE	19.25	19.25			
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	5,116	5,116			
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	5,116	5,116			
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	5,116	5,116			
* 25100115	MULCH, METHOD 2	ACRE	146	146			
* 25100630	EROSION CONTROL BLANKET	SQ YD	117,884	117,884			
* 25200200	SUPPLEMENTAL WATERING	UNIT	1800	1800			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	11,370	11,370			
28000305	TEMPORARY DITCH CHECKS	FOOT	1060	1060			
28000400	PERIMETER EROSION BARRIER	FOOT	29,350	29,350			
28000500	INLET AND PIPE PROTECTION	EACH	58	58			
28000510	INLET FILTERS	EACH	32	32			

* SPECIALTY ITEM

⚠ REVISED 6-7-11

FILE NAME = c:\pw_work\pwidot\owenbj\dms64842\D878691-S00.dgn	USER NAME = owenbj	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/25/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
270	60-1B-1	MADISON	712	6
		CONTRACT NO. 76A91		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		