

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		ACRIM 0004 L&L 90% FED 10% STATE	ACRBT 0011 L&L 90% FED 10% STATE	ACRBT 0040 L&L 90% FED 10% STATE
44004250	PAVED SHOULDER REMOVAL	SQ YD	25709	25709		
44201823	CLASS D PATCHES, TYPE I, 15 INCH	SQ YD	425	425		
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SQ YD	425	425		
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SQ YD	425	425		
44201833	CLASS D PATCHES, TYPE IV, 15 INCH	SQ YD	425	425		
44213200	SAW CUTS	FOOT	10,280	10,280		
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	6571	6571		
48203005	HOT-MIX ASPHALT SHOULDERS, 2"	SQ YD	10989	10989		
48203039	HOT-MIX ASPHALT SHOULDERS, 10 1/2"	SQ YD	8219	8219		
48300700	PORTLAND CEMENT CONCRETE SHOULDERS 12"	SQ YD	23201	23201		
48301000	PROTECTIVE COAT	SQ YD	47659	47659		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	2		2	
50102400	CONCRETE REMOVAL	CU YD	44.8			44.8
50104650	SLOPE WALL REMOVAL	SQ YD	3175		3175	
50157300	PROTECTIVE SHIELD	SQ YD	10,700		10,700	
50200100	STRUCTURE EXCAVATION	CU YD	3603		83	3520
50200300	COFFERDAM EXCAVATION	CU YD	16671		16671	
50202901	COFFERDAM (LOCATION - 1)	EACH	1		1	
50202902	COFFERDAM (LOCATION - 2)	EACH	1		1	
50300225	CONCRETE STRUCTURES	CU YD	8224.1		7538	686.1
50300255	CONCRETE SUPERSTRUCTURE	CU YD	6463.8		6469.8	
50300260	BRIDGE DECK GROOVING	SQ YD	19272		19272	
50300265	SEAL COAT CONCRETE	CU YD	6101.2		6101.2	
50300300	PROTECTIVE COAT	SQ YD	23216		23216	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	195000		195000	
50500505	STUD SHEAR CONNECTORS	EACH	36090		36090	
50800105	REINFORCEMENT BARS	POUND	740766		719170	21596
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3490,790		3,422,680	68110
50800515	BAR SPLICERS	EACH	172		172	
50901750	PARAPET RAILING	FOOT	1084			1084
51100100	SLOPE WALL 4 INCH	SQ YD	884		884	
51200959	FURNISHING METAL SHELL PILES 14" X 0.312"	FOOT	4527		4527	
51202305	DRIVING PILES	FOOT	4527		4527	