

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		0004 LS1 90% FED. 10% STATE	0011 LIC 90% FED. 10% STATE	0040 LIC 90% FED. 10% STATE	0021 LS1 90% FED. 10% STATE
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	144	144			
* 78200430	GUARDRAIL MARKERS, TYPE C	EACH	18	18			
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	8			
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	8716	8716			
80300100	LOCATING UNDERGROUND CABLE	FOOT	22221	22221			
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	2	2			
81012400	CONDUIT IN TRENCH, 1 1/4" DIA., PVC	FOOT	137				137
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	985	985			
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	545	545			
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	45	15			30
81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	780	780			
81021350	CONDUIT PUSHED, 3" DIA., PVC	FOOT	115				115
81100300	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., GALVANIZED STEEL	FOOT	240	240			
81200120	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	10500	10500			
81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	6	6			
81304100	JUNCTION BOX EMBEDDED IN STRUCTURE 12" X 12" X 6"	EACH	30	30			
81400100	HANDHOLE	EACH	16	16			
81400200	HEAVY-DUTY HANDHOLE	EACH	4				4
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	34	34			
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	2	2			
* 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	10600	10600			
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	1000	1000			
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	20636	20456			180
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	20	20			
* 82103900	LUMINAIRE, SODIUM VAPOR, MULTI MOUNT, 250 WATT	EACH	100	100			
* 82500360	LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 100AMP	EACH	1	1			
* 82500400	LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 100AMP (DUAL)	EACH	1	1			
83009500	LIGHT POLE, ALUMINUM, 45FT M.H., 12 FT. MAST ARM	EACH	59	59			
83060830	LIGHT POLE, GALVANIZED STEEL, 45 FT. M.H. TENON MOUNT	EACH	2	2			
83009600	LIGHT POLE, ALUMINUM, 45FT M.H., 15 FT. MAST ARM	EACH	7	7			
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	451	451			

*SPECIALTY ITEM

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -			270	60-1B-1	MADISON	712	12	
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -			SCALE: SHEET NO. OF SHEETS STA. TO STA.			CONTRACT NO. 76A91		
	PLOT DATE = #DATE#	DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					