

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		0004 L&I 90% FED. 10% STATE	0011 L&I 90% FED. 10% STATE	0040 L&I 90% FED. 10% STATE	0021 L&I 90% FED. 10% STATE
X0326094	RELOCATE EXISTING ITS CONTROLLER CABINET	EACH	1	1			
X0326104	RELOCATE RADAR DETECTOR SYSTEM	EACH	3	3			
X0326259	DIGITAL VIDEO ENCODER	EACH	4	4			
X0326342	DIGITAL VIDEO DECODER	EACH	1	1			
X0326542	METAL GRATING	L SUM	1		1		
X0326657	RELOCATE SIGN, SPECIAL	EACH	18	18			
X0326871	SOLAR EQUIPMENT	L SUM	1			1	
X0326912	3000 LAYER 2 SWITCH	EACH	2	2			
X0326935	CROSSHOLE SONIC LOGGING	EACH	30		30		
X0327096	ETHERNET MODEM	EACH	6	6			
X0350810	BOLLARD REMOVAL	EACH	6	6			
X0502600	TEMPORARY LIGHTING	L SUM	1	1			
X2010350	TREE REMOVAL, ACRES (SPECIAL)	ACRE	1	1			
X2040805	FURNISHED EXCAVATION, SPECIAL	CU YD	49688	49688			
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	1264		1264		
X2111000	TOPSOIL EXCAVATION	CU YD	3432	3432			
X2800510	INLET FILTER CLEANING	EACH	20	20			
X4832500	PORTLAND CEMENT CONCRETE SHOULDERS 12" (SPECIAL)	SQ YD	616	616			
X5080600	MECHANICAL SPLICERS	EACH	2512		2512		
X6370279	CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT (SPECIAL)	FOOT	933	933			
X6380200	RELOCATE MODULAR GLARE SCREEN SYSTEM	FOOT	1800	1800			
X6650202	WOVEN WIRE FENCE REMOVAL	FOOT	3107	3107			
X6660445	RIGHT OF WAY AND PROPERTY CORNERS	EACH	17	17			
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	42	42			
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1			
X7030025	WET REFLECTIVE TEMPORARY TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	40	40			
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	71045	71045			
X7030040	WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 INCH	FOOT	794	794			
X7030055	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH	FOOT	224	224			
X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	48963	48963			