

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		0004 L1C 90% FED. 10% STATE	0011 L1C 90% FED. 10% STATE	0040 L1C 90% FED. 10% STATE	0021 L1C 90% FED. 10% STATE
* X7830076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	2472	2472			
* X7830078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	FOOT	241	241			
X8100065	CONDUIT IN TRENCH, 4" DIA., PVC TYPE C	FOOT	5115	5115			
X8102020	CONDUIT PUSHED, 4" DIA., PVC SCHEDULE 80	FOOT	45	45			
* X8260110	NAVIGATION LIGHTING SYSTEM	L SUM	1	1			
* X8710075	FIBER OPTIC CABLE IN CONDUIT, 72 COND. S.M. F.O.	FOOT	11900	11900			
Z0004002	BOLLARDS	EACH	4	4			
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	80	80			
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	160	160			
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	76		76		
Z0018800	DRAINAGE SYSTEM	L SUM	1		1		
Z0019600	DUST CONTROL WATERING	UNIT	999	999			
Z0026346	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1			
* Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	12	12			
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	34	34			
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	764	764			
Z0034210	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	19560		19560		
Z0034605	MODULAR EXPANSION JOINT 21"	FOOT	176		176		
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	392		392		
Z0062456	TEMPORARY PAVEMENT	SQ YD	115	115			
Z0065100	SETTLEMENT PLATFORMS	EACH	7			7	
Z0065765	SLOTTED DRAIN 18" WITH VARIABLE SLOT	FOOT	903	903			
* Z0076600	TRAINNEES	HOOR	5000	5000			

\* SPECIALTY ITEM  
■ 0042

FILE NAME = #FILE#	USER NAME = #USER#	DESIGNED - DRAWN -	REVISED - REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE. 270	SECTION 60-1B-1	COUNTY MADISON	TOTAL SHEETS 712	SHEET NO. 14A
		CHECKED - DATE -	REVISED - REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		CONTRACT NO. 76A91		