

MAINTENANCE OF TRAFFIC PAVEMENT MARKING SCHEDULE

LOCATION	PAVEMENT MARKING REMOVAL (SQ FT)	TEMPORARY PAVEMENT MARKING - LINE 4"		EPOXY PAVEMENT MARKING - LINE 4"		LETTERS AND SYMBOLS (SQ FT)	WET REFLECTIVE TEMPORARY TAPE, TYPE III						TEMPORARY INFORMATION SIGNING (SQ FT)	MODULAR GLARE SCREEN SYSTEM (FOOT)	RELOCATE MODULAR GLARE SCREEN SYSTEM (FOOT)	
		WHITE (FOOT)	YELLOW (FOOT)	WHITE (FOOT)	YELLOW (FOOT)		4 INCH			6 INCH		24 INCH				
							WHITE (FOOT)	YELLOW (FOOT)	BLACK (FOOT)	WHITE (FOOT)	BLACK (FOOT)	WHITE (FOOT)				BLACK (FOOT)
MOT STAGE 4																
MOT STAGE 4 SHEET 1		600	300													
MOT STAGE 4 SHEET 2		1,625	1,000													
MOT STAGE 4 SHEET 3																
MOT STAGE 4 SHEET 4																
MOT STAGE 4 SHEET 5																
MOT STAGE 4 SHEET 6	176	467	234													
MOT STAGE 4 SHEET 7	647	5,700	2,850													
MOT STAGE 4 SHEET 8	190	987	608													
MOT STAGE 4 SHEET 9																
MOT STAGE 4 SHEET 10																
MOT STAGE 4 SHEET 11																
MOT STAGE 4A																
MOT STAGE 4A SHEET 1								500	250							
MOT STAGE 4A SHEET 2								2,600	1,300							
MOT STAGE 4A SHEET 3								800	400							
MOT STAGE 4A SHEET 4																
MOT STAGE 4A SHEET 5																
MOT STAGE 4A SHEET 6																
MOT STAGE 4A SHEET 7								5,331	2,737						900	
MOT STAGE 4A SHEET 8								804	230							
MOT STAGE 4A SHEET 9																
MOT STAGE 4A SHEET 10																
MOT STAGE 4A SHEET 11																
MOT STAGE 5																
MOT STAGE 5 SHEET 1																
MOT STAGE 5 SHEET 2								1,200	600							
MOT STAGE 5 SHEET 3								800	400							
MOT STAGE 5 SHEET 4																
MOT STAGE 5 SHEET 5								1,324								
MOT STAGE 5 SHEET 6								1,400								
MOT STAGE 5 SHEET 7								5,984	2,848							
MOT STAGE 5 SHEET 8								604	230							
MOT STAGE 5 SHEET 9																
MOT STAGE 5 SHEET 10																
MOT STAGE 5 SHEET 11																
MOT STAGE 6																
MOT STAGE 6 SHEET 1																
MOT STAGE 6 SHEET 2																
MOT STAGE 6 SHEET 3																
MOT STAGE 6 SHEET 4																
MOT STAGE 6 SHEET 5																
MOT STAGE 6 SHEET 6								152								
MOT STAGE 6 SHEET 7								450	225							
MOT STAGE 6 SHEET 8								150	75							
MOT STAGE 6 SHEET 9								1,710	1,435	2,475		48	48			
MOT STAGE 7																
MOT STAGE 7 SHEET 1								1,494	2,450							
MOT STAGE 7 SHEET 2								325	325							
SUMMARY																
TOTAL	8,716	39,090		30,331		37		64,586		722		204		764	1,800	1,800
CONTINGENCY (SEE NOTE)		3,909		7,583		4		6,459		72		20				
GRAND TOTAL	8,716	42,999		37,914		41		71,045		794		224		764	1,800	1,800

NOTE: 10% CONTINGENCY FOR TEMPORARY PAVEMENT MARKINGS AND WET REFLECTIVE TAPE TYPE III, TO ACCOUNT FOR DAMAGE TO MARKINGS, 25% FOR EPOXY MARKINGS DUE TO THE LENGTH OF TIME THAT THEY ARE USED.

FILE NAME = 0876A91-SHT-SCH00-09.DGN

USER NAME = sbilven

DESIGNED SJM

REVISED -07-30-10

DRAWN BAH

REVISED - 04-20-11

PLOT SCALE = #SCALE*

CHECKED SJM

REVISED -

PLOT DATE = 4/28/2011

DATE 06-30-10

REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES
INTERSTATE 270**

SCALE: SHEET NO. 11 OF 11 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
270	60-1B-1	MADISON	712	27e
CONTRACT NO. 76A91			ILLINOIS FED. AID PROJECT	