SIGN DETAIL
1:60



SIGN NUMBER	xx	
WIDTH x HGHT.	18'-6" x 11'-6"	
BORDER WIDTH	2"	
CORNER RADIUS	12"	
MOUNTING	Ground	
BACKGROUND	TYPE:	Reflective
	COLOR:	Green
LEGEND/BORDER	TYPE:	Reflective
	COLOR:	White/White

SYMBOL	ROT	X	Y	WID	HT
M1_1	0	38	79.6	45	36

Panel Style: guide_exp_advance_a.ssi
Dimensions are in inches.tenths

BORDER
R = 12"
Thick 2"

Letter locations are panel edge to lower left corner

FONT:
(1) Clearview Hwy-4-W
(2) Clearview Hwy-5-W

LETTER POSITIONS (X)

W	E	S	T								LENGTH	SERIES/SIZE
101	125.8	138.2	151.6								60.6	Clearview Hwy-4-W 18,15
S	t		C	h	a	r	l	e	s			Clearview Hwy-5-W
24.7	43.5	53.3	74.7	96.9	117.1	138.2	153.2	164.7	184.5		172.5	2016.3
N	E	X	T		R	I	G	H	T			Clearview Hwy-4-W
58.2	71.7	81.3	92.9	100.9	112.5	124.5	130.5	144	155.8		105.6	12

FILE NAME = D876A91-Sht-MOTDET07.dgn	USER NAME = mtuch	DESIGNED - JC	REVISED -
		DRAWN - BH	REVISED -
	PLOT SCALE = $SCALE$	CHECKED -	REVISED -
	PLOT DATE = Thursday, March 17, 2011 07:41:5	DATE - 1-01-11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUGGESTED MAINTENANCE OF TRAFFIC
MISCELLANEOUS DETAIL

SCALE: | SHEET NO. 7 OF 9 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
270	60-1B-1	MADISON	712	208
		CONTRACT NO. 76A91		
	ILLINOIS	FED. AID PROJECT		